

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01000

GENERAL

PART 1 GENERAL

- 1.1 DESCRIPTION OF WORK
- 1.2 ORGANIZATION OF SPECIFICATIONS
- 1.3 REFERENCES
- 1.4 SUBMITTALS
- 1.5 PERMITS

PART 2 PRODUCTS

- 2.1 APPROVAL OF MATERIALS OR ALTERNATES
- 2.2 WARRANTIES

PART 3 EXECUTION

- 3.1 GROUNDS AND ROADWAYS
  - 3.1.1 Availability of Grounds
  - 3.1.2 Drainage Facilities
  - 3.1.3 Roadways
    - 3.1.3.1 Traffic hazards
    - 3.1.3.2 Haul routes
  - 3.1.4 Texas Crossing
  - 3.1.5 Sanitary Sewer
- 3.2 DISPOSAL OF DEBRIS AND WASTE
  - 3.2.1 Disposal offsite for useful purposes
  - 3.2.2 Disposal in a locally operated sanitary landfill
  - 3.2.3 Disposal of Solid Construction Debris and Waste
- 3.3 EXISTING UTILITIES
  - 3.3.1 General
  - 3.3.2 Buried Utilities
  - 3.3.3 Interruption of Services
  - 3.3.4 Minnesota One Call Excavation Notice System
- 3.4 SCHEDULING
  - 3.4.1 General
  - 3.4.2 Notification
- 3.5 CONSTRUCTION RESTRICTIONS
  - 3.5.1 Blasting
  - 3.5.2 Protection of Trees
    - 3.5.2.1 Restoration of Damaged Trees
- 3.6 SHORING
  - 3.6.1 General
  - 3.6.2 Responsibility
  - 3.6.3 Removal

### 3.7 DEWATERING OPERATIONS

#### 3.7.1 Scope

#### 3.7.2 Requirements

##### 3.7.2.1 Design

##### 3.7.2.2 Regulations

##### 3.7.2.3 Operation

##### 3.7.2.4 Removal

#### 3.7.3 Geologic Information

#### 3.7.4 Channel Excavation Dewatering Plan

#### 3.7.5 Sanitary Siphon Dewatering Plan

#### 3.7.6 Liability

#### 3.7.7 Related Work

### 3.8 SURVEYS

#### 3.8.1 Field Layout

##### 3.8.1.1 Alignment Changes

#### 3.8.2 Utility As-builts

#### 3.8.3 Quantity surveys

-- End of Section Table of Contents --

## SECTION 01000

### GENERAL

#### PART 1 GENERAL

##### 1.1 DESCRIPTION OF WORK

The work of this contract includes but is not limited to construction of cutoff channel, construction of cutoff channel "Texas Crossing," construction of excavated material disposal area, installation of a manhole, and removal and replacement of an underground sewer.

##### 1.2 ORGANIZATION OF SPECIFICATIONS

The specifications which govern the materials and equipment to be furnished and the work to be performed under this contract are listed in the Table of Contents. No attempt has been made in the specifications to segregate work to be performed by any trade, craft, or subcontractor. Any segregation between the trades or crafts shall be solely a matter for agreement between the Contractor, Contractor's employees, and subcontractors.

##### 1.3 REFERENCES

Reference to the standards, specifications, or codes of any technical society, organization, or association, or local, state, or Federal authority shall mean the specific edition or revision listed.

##### 1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

###### SD-01 Preconstruction Submittals

###### Sanitary Siphon Dewatering plan;

The submittal requirements are described in PARAGRAPH: DEWATERING OPERATIONS. Additional dewatering plans shall be submitted for other areas or phases of the contract where wells, wellpoints, or related systems are required.

###### Channel Excavation Dewatering plan; G,GT

The submittal requirements are described in PARAGRAPH: DEWATERING OPERATIONS.

Shoring plan;

The submittal requirements are described in PARAGRAPH: SHORING.

Sanitary Sewer Interruption Plan; G,GEN

The submittal requirements are described in PARAGRAPH: SANITARY SEWER.

#### SD-11 Closeout Submittals

Utility As-Builts;

The Utility As-Builts are described under PARAGRAPH: SURVEYS.

### 1.5 PERMITS

The City of Crookston has applied for a protected waters permit from the Minnesota Department of Natural Resources.

## PART 2 PRODUCTS

### 2.1 APPROVAL OF MATERIALS OR ALTERNATES

Requests for approval of materials and products, or substitutes thereof, will not be considered prior to award of the contract.

### 2.2 WARRANTIES

Any items that are submitted for review or approval of the Contracting officer should include a copy of the manufacturer's standard warranty if one is available.

## PART 3 EXECUTION

### 3.1 GROUNDS AND ROADWAYS

#### 3.1.1 Availability of Grounds

The boundary limits of the grounds made available for the Contractor's use during the life of the contract are shown on the drawings. Any additional rights-of-way or grounds desired by the Contractor shall be obtained by the Contractor at its own expense, and copies of agreements for the use of such rights-of-way shall be furnished to the Contracting Officer before entering thereon. Such agreements shall clearly relieve the Government of any responsibility for damages resulting from the use of the grounds.

#### 3.1.2 Drainage Facilities

Insofar as natural drainage from the protected areas is obstructed by contract operations, it shall be the Contractor's responsibility to make

adequate provision for accommodating such drainage in a satisfactory manner during the life of this contract, either by temporary means or by use of the permanent construction and operation of the permanent facilities.

### 3.1.3 Roadways

#### 3.1.3.1 Traffic hazards

When continuous haul operations or other condition created by the Contractor's operations result in interference or hazard to traffic on streets and highways, beyond that of ordinary public usage, the Contractor shall erect warning signs and provide flagging services as necessary to safeguard the public as required in SECTION 01500: TEMPORARY CONSTRUCTION FACILITIES.

#### 3.1.3.2 Haul routes

The Contractor shall be responsible for securing all permits required along haul routes. The Contractor shall be the sole permittee and shall be responsible for meeting all obligations of the permits. A copy of each permit shall be submitted to the Contracting Officer. The Contractor, as between the Government and the Contractor, has sole responsibility for damage or deterioration of the Contractor's haul routes. Dust control shall be provided as stated in SECTION 01355: ENVIRONMENTAL PROTECTION.

#### 3.1.4 Texas Crossing

Contractor shall not use the Texas crossing in its finished state for earth moving operations. As such, Contractor shall construct the Texas crossing (subgrade preparation, geotextile, aggregate surfacing) only after completion of earthwork operations.

#### 3.1.5 Sanitary Sewer

Interruption of the sanitary sewer between existing Manholes P2 and P3 is required for construction of the cutoff channel. Sanitary service interruption shall be kept to the minimum time possible. Sanitary sewer interruption shall not extend over more than one construction season. Contractor is not required to provide temporary sanitary service. Contractor shall request approval in writing at least 30 calendar days prior to the proposed interruption. This submittal shall fully describe all details of proposed interruption. The Contractor shall further coordinate with the City of Crookston (City) at least 10 calendar days in advance of interruption of services. Contractor shall notify the City in writing at least 30 calendar days prior to putting the new sanitary sewer syphon into service and shall again notify the City 10 calendar days in advance of putting the syphon into service.

### 3.2 DISPOSAL OF DEBRIS AND WASTE

The Contractor's attention is directed to SECTION 01355: ENVIRONMENTAL PROTECTION and to the following CONTRACT CLAUSES: PERMITS AND RESPONSIBILITIES; PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS; OPERATIONS AND STORAGE AREAS; and

CLEANING UP. Burning will not be permitted at the project site and debris or waste shall not be left on the site. Disposal of clearing and grubbing debris shall be by one of the following methods:

#### 3.2.1 Disposal offsite for useful purposes

In the interest of conservation, it is required that the Contractor make a reasonable effort to dispose of the material offsite for some useful purpose. Timber may be cut into convenient lengths and utilized for making saw logs, posts, cordwood, wood chips for paper making or other uses, or other similar use.

#### 3.2.2 Disposal in a locally operated sanitary landfill

Contractor shall select the disposal site with the approval of the Contracting Officer. The Contractor shall secure the required permits for disposal and provide copies of the permit to the Contracting Officer.

#### 3.2.3 Disposal of Solid Construction Debris and Waste

Disposal of Solid Construction Debris and Waste shall consist of removal from Government property and disposal in compliance with Federal, state, and local requirements for solid waste disposal. Contractor shall select the disposal site with the approval of the Contracting Officer.

### 3.3 EXISTING UTILITIES

#### 3.3.1 General

The Contractor shall coordinate all utility relocation requirements and make payment to the utility companies for all services, fees, and permits required to relocate and reestablish service. The Contractor shall be responsible for all costs related to protecting existing utilities. The Contractor shall coordinate with the utility representatives listed below:

Sanitary Sewer. The Contractor shall further coordinate with the City of Crookston in advance of interruption of services.

#### 3.3.2 Buried Utilities

The approximate locations of known existing buried utilities are shown on the drawings to the extent of available information at the time the drawings were prepared. (In general, no service connections are shown.) Prior to commencing excavation, the Contractor shall accurately locate all such installations. In the event the Contractor damages any existing utility lines, report thereof shall be made immediately to the Contracting Officer. If the Contracting Officer determines that repairs shall be made by the Contractor, such repairs shall be performed immediately.

#### 3.3.3 Interruption of Services

Utility services shall not be interrupted except for brief periods to facilitate cut-ins. The Contractor shall provide temporary service and shall relocate existing utilities as required to construct the work shown

and insure uninterrupted service. If interruption of services is unavoidable, the Contractor shall request approval in writing at least 30 calendar days prior to the proposed interruption. This submittal shall fully describe all details of proposed interruption and the reasons why alternatives are not feasible. The Contractor shall further coordinate with the owner of the utility and notify affected consumers at least 10 calendar days in advance of interruption of services. The Contracting Officer will not in general approve proposals which require interruption of services for more than 4 continuous hours.

#### 3.3.4 Minnesota One Call Excavation Notice System

For contract work performed within the State of Minnesota, the Contractor shall meet the requirements of Minnesota Statutes, Chapter 216D "One Call Excavation Notice System." The Gopher State One Call notification center telephone numbers are:

Metro area	(651) 454-0002
Outstate	(800) 252-1166

#### 3.4 SCHEDULING

##### 3.4.1 General

It shall be the responsibility of the Contractor to schedule and execute the work, incorporating the necessary requirements set forth in these specifications. The Contractor shall develop and submit a schedule in accordance with CONTRACT CLAUSE: SCHEDULES FOR CONSTRUCTION CONTRACTS.

##### 3.4.2 Notification

The Contractor shall inform the Government in writing within 5 days after receipt of notice to proceed and before work begins as to which hours of the day and days of the week work under this contract will be performed. The Contractor shall notify the Government at least 24 hours before work is to be conducted on overtime, in multiple shifts, on weekends, or on Federal Government holidays.

#### 3.5 CONSTRUCTION RESTRICTIONS

##### 3.5.1 Blasting

Blasting will not be permitted.

##### 3.5.2 Protection of Trees

Trees to be protected shall be determined and staked by the Contracting Officer. The following measures shall be implemented for tree protection and shall be addressed in the Environmental Protection Plan required under SECTION 01355:

- a. The trees shall be protected from wounds to the bark and foliage.
- b. The critical root zone shall be protected from compaction and grading.

- c. Changes in temporary site drainage and ponding shall be minimized to the extent possible that it effects the protected trees.

The critical root zone of trees designated to be protected shall be surrounded by a high visibility fence 4 feet in height, supplied and erected by the Contractor. The critical root zone shall be defined by an area extending 1.5 feet radius from each tree for each inch of Diameter at Breast Height (DBH). The fence shall be securely erected and installed prior to any movement through the project site by construction vehicles or equipment, and remain in place until construction and clean-up are completed. The critical root zone shall remain free of all construction activities including trenching, staging, stockpiling and storage of materials. Vehicles and equipment shall not drive or park within the critical root zone. Variation to the critical root zone size or configuration will only be permitted where it is absolutely necessary for construction of the project, and requires approval of the Contracting Officer. Short duration alterations of the critical root zone involving wood chips and limited equipment travel shall be submitted in writing for approval.

The Contractor shall not operate equipment in vegetated areas outside the work limits.

#### 3.5.2.1 Restoration of Damaged Trees

Any existing tree designated to be protected that is damaged by the Contractor's operations shall be replaced. Trees will be considered damaged if the critical root zone in cohesive soils is compacted, if there are significant wounds that could contribute to rot, or if distress (evident by reduced growth or other observations of distress documented by a forester) is observed prior to closing the contract. Trees shall be replaced in kind on a caliper inch per caliper inch basis (DBH) (i.e. one 6-inch red oak shall be replaced with two 3-inch red oaks, three 2-inch red oaks, or six 1-inch red oaks). Replacement trees shall be planted and guaranteed with the Contractor's standard warranty. Replacement tree size and location will be determined and staked by the Contracting Officer. Repair by pruning, aeration, soil conditioning, or other recommendation from a qualified forester will be considered as substitution for replacement by the Contracting Officer.

### 3.6 SHORING

#### 3.6.1 General

At locations where shoring is not specifically required by the contract documents to safeguard adjacent structures, the Contractor may at its own option employ shoring for protecting work areas within excavations in lieu of performing excavation to safe and stable side slopes. The Contractor shall construct all shoring required in performing the excavations. Shoring shall be constructed in accordance with the safety requirements of EM 385-1-1.

#### 3.6.2 Responsibility



The Contractor shall be responsible for design and maintenance of all shoring which the Contractor proposes to install. Plans and design computations for all shoring used shall be submitted in accordance with SECTION 01330: SUBMITTAL PROCEDURES at least 30 days prior to installation.

### 3.6.3 Removal

Unless otherwise authorized, all sheeting and bracing shall be removed when backfill is completed.

## 3.7 DEWATERING OPERATIONS

### 3.7.1 Scope

The disposal area fill is intended to be placed and compacted to a density similar to the native soils. The moisture content of the channel excavation shall be controlled so that the fill is generally placed at a moisture content less than or equal to the native soils.

The Contractor shall design, furnish, install and operate dewatering systems in conjunction with associated cofferdams, shoring, and other related work. Surface drainage shall be controlled by rerouting storm water runoff or diverting natural drainage, as necessary.

### 3.7.2 Requirements

Control of groundwater shall be accomplished in a manner that will provide suitable working conditions for construction, preserve the strength of the foundation soils, will not cause instability of excavations. Suitable working conditions for construction will provide a dry or moist subgrade free of standing, percolating, or running water to the extent practicable during excavation, and placement and compaction of backfill.

#### 3.7.2.1 Design

If conditions warrant, and if not otherwise specified in the contract documents, dewatering may consist of collection in sumps or trenches, and open pumping. Sumps, trenches and running water shall not jeopardize erosion or ground loss near foundations, pipes, or other structures. Open pumping will not be permitted if it results in boils, seepage in concrete placement areas, loss of fines, softening of the ground, instability of slopes, or interference with orderly progress of the construction.

#### 3.7.2.2 Regulations

Compliance with all regulations shall be incidental to the dewatering work. Disposal of water shall be in accordance with SECTION 01355: ENVIRONMENTAL PROTECTION and all applicable regulations. Well abandonment shall seal aquifers and confining layers in compliance with environmental regulations and permits.

#### 3.7.2.3 Operation

Upon installation and commencement of dewatering operations, the system

shall be operated continuously (24 hours/day, 7 days/week) until the structure and backfill are completed to the groundwater elevation. The Contractor shall be responsible for maintaining the system.

#### 3.7.2.4 Removal

Upon completion of the work, well casing and screens shall be withdrawn, and all equipment shall be removed (including related temporary cofferdams, shoring, etc.)

#### 3.7.3 Geologic Information

Ground water elevations shown on the boring logs are those encountered at the time the borings were taken. Because groundwater elevations are dependent upon hydrologic conditions, variations in the water table should be expected. For work near rivers and navigable waterways, refer to the hydrographs included with the contract drawings. It shall be the Contractors responsibility to perform the necessary dewatering operations irrespective of the water elevations at the time of the work. However, nothing in this clause prohibits the Contractor from receiving a time extension under the Default clause, the Time Extensions for Unusually Severe Weather clause, or any other clause in this contract.

Cutoff Channel 1 will be constructed through saturated silty sand layers extending from approximately elevation 837 feet to the groundwater table near elevation 845 feet as indicated in borings 93-9M, 93-10M, and 93-13M. These layers are typically fine to medium coarse sand, silty, saturated, loose to medium dense, with D10 sizes ranging between 0.07 mm and 0.15 mm.

#### 3.7.4 Channel Excavation Dewatering Plan

The Channel Excavation Dewatering plan shall include the following items:

1. excavation sequence
2. layout (including the relationship to site improvements and construction operations)
3. type, sizes, depth and spacing of dewatering devices
4. number and capacity of pumps
5. description of discharge point (weirs, sedimentation basin, etc.)
6. type and location of monitoring equipment
7. removal and abandonment plans

#### 3.7.5 Sanitary Siphon Dewatering Plan

The Sanitary Siphon Dewatering plan shall include the following items:

1. layout (including the relationship to site improvements and construction operations)
2. type, sizes, depth and spacing of dewatering devices
3. number and capacity of pumps
4. description of discharge point (weirs, sedimentation basin, etc.)
5. type and location of monitoring equipment
6. removal and abandonment plans

### 3.7.6 Liability

Government review of the proposed dewatering system will not relieve the Contractor of full responsibility for the adequacy of the dewatering operations. The Contractor shall be responsible for dewatering effects on adjacent properties, including but not limited to blockage of easements, erosion or sedimentation of ditches, and encroachment onto private property by flooding from pump outlets and sedimentation basins.

### 3.7.7 Related Work

Shoring, trench support systems, cofferdams and diversion structures shall be coordinated with the dewatering effort to provide safe and reliable conditions.

## 3.8 SURVEYS

### 3.8.1 Field Layout

The Contractor shall layout the work from the Government established bench marks in accordance with CONTRACT CLAUSE: LAYOUT OF WORK. The construction of each feature of work shall follow the alignments as indicated on the drawings. The Contractor shall have in place, at least 7 calendar days prior to commencing construction operations, sufficient stakes and markings to enable the Contracting Officer to observe the field layout of the alignment and limits of each feature of work. For each feature of work, these stakes shall define areal limits such that the Contracting Officer can easily determine, without additional surveys, if alignment and/or limit adjustments need to be made. For embankments, levees, floodwalls, and similar work, these stakes shall define centerline, stationing, outermost fill/cut limits, and work limits. For buildings and similar work, the building corners and grid lines shall be staked. General site work shall be staked to define staging areas, storage areas, and other area limits as directed. The Contracting Officer may waive these requirements for certain areas. The layout shall be sufficient for the Contracting Officer to mark trees, vegetation and other features to be left undisturbed. No work shall take place without approval of field layout by the Contracting Officer.

#### 3.8.1.1 Alignment Changes

The Government reserves the right to make changes in the alignment of any feature of work as may be found necessary during the course of the contract. If it becomes necessary, through no fault of the Contractor, to abandon a line, location or feature on which work has been done, an equitable adjustment for completed work will be made. No alignment changes or abandonment shall take place without prior written notice from the Contracting Officer.

#### 3.8.2 Utility As-builts

An as-built field survey of all utilities shall be conducted after installation to determine the final locations and elevations of all utility structures such as manholes, catch basins, hydrants, gate valves, cleanouts, service connections, and other special controls or structures.

Final elevations shall be determined for all sewer inverts and castings. Locations shall be shown using the same convention as the original contract drawings (typically stationing and offset from known centerline). If no convention is used in the contract drawings, locations shall be tied to at least 2 permanent landmarks.

#### 3.8.3 Quantity surveys

The Contractor shall perform quantity and tolerance verification surveys for all features of work in accordance with CONTRACT CLAUSE: QUANTITY SURVEYS--ALTERNATE I. Unless changed by the Contracting Officer, the Contractor shall provide cross sections at 100 foot intervals to verify the required section. Areas where payment for material is specified by volume, and/or weight, shall be surveyed by the Contractor, prior to commencement of construction of each feature and upon completion of each feature, in enough detail to accurately determine quantities and verify the required section. The Contractor shall also plot each cross section from the survey notes at a scale of 1" = 10' and provide a copy of the survey notes and cross sections to the Contracting Officer within 10 days after completion of the survey.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01270

MEASUREMENT AND PAYMENT

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 COMPENSATION
- 1.3 FIELD MEASUREMENT
- 1.4 MEASUREMENT BY WEIGHT
- 1.5 MEASUREMENT UNITS
- 1.6 UNIT PRICES
  - 1.6.1 Clearing and Grubbing
  - 1.6.2 Dewatering
  - 1.6.3 Demolition
  - 1.6.4 Common Excavation/Disposal
  - 1.6.5 Impervious Fill
  - 1.6.6 Geotextile
  - 1.6.7 Aggregate Surfacing
  - 1.6.8 Riprap
  - 1.6.9 Riprap Bedding
  - 1.6.10 Granular Fill
  - 1.6.11 Trench Excavation/Backfill
  - 1.6.12 20" HDPE Pipe
  - 1.6.13 Select Granular Bedding Material
  - 1.6.14 Sanitary Sewer Manhole
  - 1.6.15 Sanitary Sewer Connections
  - 1.6.16 Reinforced Concrete Arch Culvert
  - 1.6.17 Topsoil and Seeding
  - 1.6.18 Erosion control matting
  - 1.6.19 Bonds

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section Table of Contents --

## SECTION 01270

### MEASUREMENT AND PAYMENT

#### PART 1 GENERAL

##### 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

#### NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST HB 44	(1997) NIST Handbook 44: Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices
------------	--

##### 1.2 COMPENSATION

The payment provided for in the contract shall constitute full compensation for furnishing all materials and for performing all work under the contract in a complete and acceptable manner. The contract work shall include providing plant, equipment, tools, supplies, labor, supervision, incidental materials, quality control, environmental protection, and meeting safety requirements, and for performing all work required for which separate payment is not otherwise provided. Compensation for all work shown, specified, or essential to completion of the project (whether or not the specific material or operation is indicated) shall be included on the bidding schedule. The payment provided for in the contract includes compensation for all risk, loss, damage, and expense arising out of the nature of the work or its prosecution, subject to conditions of the contract. Payment for each contract line item will constitute full compensation for furnishing the materials and constructing the work complete in place as specified.

##### 1.3 FIELD MEASUREMENT

The Contractor shall provide field surveys for quantity determination as specified in SECTION 01000.

##### 1.4 MEASUREMENT BY WEIGHT

Bulk materials paid for by weight will be measured by weighing each truck load on approved scales before being placed in the work. Scales shall be of sufficient length to permit simultaneous weighing of all axle loads and shall be sensitive to a change in load of 0.2 percent throughout the range

of the scales. The scale's accuracy shall conform to the applicable requirements of NIST HB 44 and shall be certified by scale servicing company or by an inspector of the State Inspection Bureau. Each load shall be accompanied by a delivery ticket certified by the weighmaster. Delivery tickets shall be collected by the Contractor, and copies thereof shall be furnished to the Contracting Officer. As a minimum, each ticket shall contain the following information:

- (1) Date and time.
- (2) Vehicle number.
- (3) Gross weight.
- (4) Vehicle tare weight.
- (5) Net weight.
- (6) Job total for material weighed.
- (7) Signature of weighmaster.

#### 1.5 MEASUREMENT UNITS

When materials are measured in units other than the measurement units specified as the basis of payment, the measured quantities shall be converted to the specified unit of measure. Factors for conversions from one basis or unit of measurement to another shall be approved by the Contracting Officer.

#### 1.6 UNIT PRICES

Payment items for the work of this contract are listed in the BIDDING SCHEDULE and described below. The payment items provided for on the bidding schedule embody the majority of the work; but the work descriptions provided below do not specifically discuss all incidental work required to complete the contract work.

##### 1.6.1 Clearing and Grubbing

Clearing and grubbing will not be measured for separate payment and shall be performed on a lump sum basis, complete. Payment will be made at the contract unit price for clearing and grubbing, and this price shall constitute full compensation for all labor, equipment, tools, and incidentals necessary to complete the work specified herein.

##### 1.6.2 Dewatering

Dewatering will not be measured for separate payment and shall be performed on a lump sum basis, complete. This work shall include installation, operation, maintenance, and removal of dewatering devices, to provide satisfactory conditions to complete the work as specified.

##### 1.6.3 Demolition

Demolition will not be measured for separate payment and shall be performed on a lump sum basis, complete. This work shall include removal and disposal of existing pipes, culverts, and appurtenances.

##### 1.6.4 Common Excavation/Disposal

Payment will be made at the contract unit price for material removed from the excavation and disposed of as herein specified. The unit of measurement for excavation will be the cubic yard. The volume shall be computed by the average end area method from cross sections taken before and after the cutoff channel and Texas crossing excavation operations. The volume to be paid for will be the number of cubic yards of material measured in its original position. All excavation shall be unclassified regarding material type and consistency. The measurement will not include the volume of material that is scarified or plowed and reused in-place. Separate excavation, hauling, and spreading or piling of topsoil and related miscellaneous operations will be covered under the contract unit price for common excavation and disposal.

#### 1.6.5 Impervious Fill

Impervious fill will be paid for at the contract unit price per cubic yard for impervious fill. Impervious fill will be measured by the cubic yard in place using the average-end-area method based on the stripping and excavation lines shown, modified to include authorized overdepth stripping, and the final lines, grades, and sections shown with the following limitations or exceptions:

- (1) Tolerances are provided only for the convenience of the Contractor and no material placed outside of the lines, grades, and sections shown as a result of the permitted tolerances will be measured for payment.
- (2) Material placed above the lines, grades, and sections shown as allowance for shrinkage will not be measured for payment.

#### 1.6.6 Geotextile

Geotextile will be paid for at the contract unit price per square yard. Measurement shall be made of the as-built surface area covered by geotextile. Allowance will be made for geotextile in anchor and/or drainage trenches; but no allowance will be made for waste, overlaps, damaged materials, repairs, or materials used for the convenience of the Contractor. This work shall include materials, delivery, storage, installation, and testing.

#### 1.6.7 Aggregate Surfacing

Aggregate Surfacing will be paid for at the contract unit price per cubic yard. Aggregate surfacing shall be measured by the as-built area determined by field surveys, multiplied by the plan thickness shown on the drawings. This work shall include material, delivery, stockpiling, placement, compaction, and testing. Aggregate surface material placed to establish or maintain haul roads, or other temporary uses to facilitate construction operations, will not be measured for payment and shall be considered incidental work.

#### 1.6.8 Riprap



Payment will be by the ton (2,000 pounds avoirdupois) of material acceptably placed within the tolerances specified. This work shall include material, hauling, stockpiling, placement, and testing.

#### 1.6.9 Riprap Bedding

Payment will be by the ton (2,000 pounds avoirdupois) of material acceptably placed within the tolerances specified. This work shall include material, hauling, stockpiling, placement, and testing. Chinking riprap at the Texas crossing will be measured and paid for as Riprap Bedding.

#### 1.6.10 Granular Fill

Granular fill will be paid for at the contract unit price per cubic yard. Granular fill shall be measured by the as-built area determined by field surveys, multiplied by the plan thickness shown on the drawings. This work shall include material, hauling, stockpiling, placement, compaction.

#### 1.6.11 Trench Excavation/Backfill

Trench excavation/backfill will be paid for at the contract unit price per linear feet. Trench excavation shall be measured by the linear feet along the centerline of the trench which is excavated to the depths and widths necessary for installation of the pipe. No increase shall be made for the extra excavation required at manholes and similar structures. This work shall include excavation, stockpiling, backfilling, compaction, installation/removal of shoring, and installation/removal of dewatering.

#### 1.6.12 20" HDPE Pipe

20" HDPE pipe will be paid for at the contract unit price per linear foot. The length of pipe installed will be measured by field surveys of the completed work. Extra pipe length in fittings or couplings shall not be measured. No extra payment will be made for bends.

#### 1.6.13 Select Granular Bedding Material

Select granular bedding material will not be measured for payment; and will be paid for at the contract lump sum price. This work shall include material, hauling, stockpiling, placement, compaction.

#### 1.6.14 Sanitary Sewer Manhole

Sanitary sewer manhole will be paid for at the contract price on a lump sum basis. This work shall include materials, delivery, storage, installation, cutting, shaping, pipe fittings, and concrete.

#### 1.6.15 Sanitary Sewer Connections

Sanitary sewer connections, disconnections, and temporary service lines will be paid for at the contract price for sanitary sewer connections on a lump sum basis. This work shall include removal and replacement of pipe, materials, installation, cutting, shaping, pipe fittings, and concrete, permits, and coordination with the City.

#### 1.6.16 Reinforced Concrete Arch Culvert

Pipe and flared end sections will be paid for at the contract price for reinforced concrete arch culvert on a lump sum basis. This work shall include materials, delivery, installation, and geotextile joint wrap.

#### 1.6.17 Topsoil and Seeding

Topsoil and seeding will be paid for at the contract unit price per acre. Topsoil and seeding will be measured for payment by field surveys of completed work. The area measured for payment will be determined by field surveys of completed work. No classification shall be given to seeding methods, seed type, or erosion control matting areas. The work shall include placement of topsoil, amendments, placement of seed, watering, and care of turf. Restoration by seeding of disturbed areas not designated on the drawings will not be measured for payment and shall be incidental to the work being performed.

#### 1.6.18 Erosion control matting

Erosion control matting will be paid for at the contract unit price per square yard. The area measured for payment will be limited to the areas designated for erosion control matting as shown on the drawings. Allowance will be made for erosion control matting in anchor trenches; but no allowance will be made for waste, overlaps, damaged materials, repairs, or materials used for the convenience of the Contractor. The work shall include pick-up and delivery of Government furnished materials, staking, and installation.

#### 1.6.19 Bonds

Bonds will be paid for on a job basis in accordance with FAR 52.232-5.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01330

SUBMITTAL PROCEDURES

PART 1 GENERAL

- 1.1 SUBMITTAL IDENTIFICATION
- 1.2 SUBMITTAL CLASSIFICATION
  - 1.2.1 Government Approved
  - 1.2.2 Information Only
- 1.3 APPROVED SUBMITTALS
- 1.4 DISAPPROVED SUBMITTALS
- 1.5 WITHHOLDING OF PAYMENT

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 GENERAL
- 3.2 SUBMITTAL REGISTER (ENG FORM 4288)
- 3.3 SCHEDULING
- 3.4 TRANSMITTAL FORM (ENG FORM 4025)
- 3.5 SUBMITTAL PROCEDURE
  - 3.5.1 Submittal Copies
  - 3.5.2 Schedule
  - 3.5.3 Shop Drawings
  - 3.5.4 Deviations
- 3.6 CONTROL OF SUBMITTALS
- 3.7 GOVERNMENT APPROVED SUBMITTALS
- 3.8 INFORMATION ONLY SUBMITTALS
- 3.9 STAMPS
- 3.10 CONTRACTOR RECORD DRAWINGS
  - 3.10.1 As-Built Shop Drawings

-- End of Section Table of Contents --

## SECTION 01330

### SUBMITTAL PROCEDURES

#### PART 1 GENERAL

##### 1.1 SUBMITTAL IDENTIFICATION

Submittals required are identified by SD numbers and titles as follows:

- SD-01 Preconstruction Submittals
- SD-02 Shop Drawings
- SD-03 Product Data
- SD-04 Samples
- SD-05 Design Data
- SD-06 Test Reports
- SD-07 Certificates
- SD-08 Manufacturer's Instructions
- SD-09 Manufacturer's Field Reports
- SD-10 Operation and Maintenance Data
- SD-11 Closeout Submittals

##### 1.2 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

###### 1.2.1 Government Approved

Governmental approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

###### 1.2.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

##### 1.3 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the CQC requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

#### 1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

#### 1.5 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

### PART 2 PRODUCTS (Not Applicable)

### PART 3 EXECUTION

#### 3.1 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

### 3.2 SUBMITTAL REGISTER (ENG FORM 4288)

At the end of this section is a submittal register (ENG Form 4288) showing items of equipment and materials for which submittals are required by the specifications; this list may not be all inclusive and additional submittals may be required. Columns "c" through "f" have been completed by the Government; the Contractor shall complete columns "a" and "g" through "i" and submit the forms to the Contracting Officer for approval within 7 calendar days after Notice to Proceed. The Contractor shall keep the submittal register up-to-date and shall submit it to the Government together with the monthly payment request. The approved submittal register will become the scheduling document and will be used to control submittals throughout the life of the contract. The submittal register and the progress schedules shall be coordinated.

### 3.3 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 30 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals. The submittal register shall provide for a reasonable timely distribution of shop drawings as they are prepared (particularly within a specific discipline, i.e.: structural, mechanical).

### 3.4 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. This form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.

### 3.5 SUBMITTAL PROCEDURE

#### 3.5.1 Submittal Copies

The Contractor shall submit 6 copies of each submittal (both government approved and for information only) unless otherwise indicated. Each transmittal shall address only one submittal item. Transmittals returned for resubmission shall be resubmitted in their entirety. When approved by the Contracting Officer, routine test reports and delivery tickets may be submitted with daily quality control reports in place of following submittal procedures under this section.

#### 3.5.2 Schedule

Shop drawings shall be submitted with ample time to secure Government approval prior to the time the items covered thereby are to be delivered to the site. Additional time should be allowed for possible resubmittal. Materials fabricated or delivered without Government approval of the shop drawing will be subject to rejection. All submittals shall be made prior to commencement of applicable work, and allow adequate time for government review acceptable to the Contracting Officer.

#### 3.5.3 Shop Drawings

Shop drawings shall be reproductions on high quality paper with clear legible print. Drawings shall generally be bordered a minimum of one inch and trimmed to neat lines. Shop drawing quality will be subject to approval. Each shop drawing, including catalog data, shall be identified with a title block including the name of the Contractor, contract number, name and location of project, and name of the item of work or structure to which the shop drawing applies. Catalog data, including specifications and full descriptive matter, may be submitted as shop drawings. Catalog data must be supplemented as necessary to include all pertinent data to verify conformance to the contract documents. When catalog data includes non applicable data, the applicable data shall be clearly indicated.

#### 3.5.4 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

#### 3.6 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

#### 3.7 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and dated. Five copies of the submittal will be retained by the Contracting Officer and 1 copy of the submittal will be returned to the Contractor.

#### 3.8 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work;

and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

### 3.9 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:



<p>CONTRACTOR</p> <p>(Firm Name)</p> <p>_____ Approved</p> <p>_____ Approved with corrections as noted on submittal data and/or attached sheets(s).</p> <p>SIGNATURE: _____</p> <p>TITLE: _____</p> <p>DATE: _____</p>
---

### 3.10 CONTRACTOR RECORD DRAWINGS

The Contractor shall maintain a separate set of marked-up full-scale contract drawings indicating as-built conditions. These drawings shall be maintained in a current condition at all times until completion of the work and shall be available for review by Government personnel at all times. All variations from the contract drawings, for whatever reason, including those occasioned by modifications, optional materials, and the required coordination between trades, shall be indicated. These variations shall be shown in the same general detail utilized in the contract drawings.

Revisions shall be shown on all drawings and details related to the changed feature. These drawings shall be neatly prepared with clear legible print.

Deleted items shall be indicated in red and added items or changed locations shall be shown in green. These drawings shall be furnished to the Contracting Officer within 30 days after the required contract completion date.

#### 3.10.1 As-Built Shop Drawings

The Contractor shall record changes to shop drawings to indicate as-built conditions. These drawings shall show all changes and revisions made up to the time the equipment is completed and accepted.

-- End of Section --

**TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES, OR MANUFACTURER'S CERTIFICATES OF COMPLIANCE**

*(Read instructions on the reverse side prior to initiating this form)*

## SECTION I - REQUEST FOR APPROVAL OF THE FOLLOWING ITEMS

*(This section will be initiated by the contractor)*

TO:	FROM:	CONTRACT NO.	CHECK ONE: <input type="checkbox"/> THIS IS A NEW TRANSMITTAL <input type="checkbox"/> THIS IS A RESUBMITTAL OF TRANSMITTAL _____
SPECIFICATION SEC. NO. (Cover only one section with each transmittal)		PROJECT TITLE AND LOCATION	CHECK ONE: THIS TRANSMITTAL IS FOR <input type="checkbox"/> FIO <input type="checkbox"/> GOV'T. APPROVAL

[illegible]

## SECTION II - APPROVAL ACTION

ENCLOSURES RETURNED <i>(List by Item No.)</i>	NAME, TITLE AND SIGNATURE OF APPROVING AUTHORITY	DATE
---	--	------

## INSTRUCTIONS

1. Section I will be initiated by the Contractor in the required number of copies.
2. Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial number for identifying each submittal. For new submittals or resubmittals mark the appropriate box; on resubmittals, insert transmittal number of last submission as well as the new submittal number.
3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288-R for each entry on this form.
4. Submittals requiring expeditious handling will be submitted on a separate form.
5. Separate transmittal form will be used for submittals under separate sections of the specifications.
6. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications--also, a written statement to that effect shall be included in the space provided for "Remarks".
7. Form is self-transmittal, letter of transmittal is not required.
8. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I.
9. U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below in Section I, column g, to each item submitted.

### THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED

A --	Approved as submitted.	E --	Disapproved (See attached).
B --	Approved, except as noted on drawings.	F --	Receipt acknowledged.
C --	Approved, except as noted on drawings. Refer to attached sheet resubmission required.	FX --	Receipt acknowledged, does not comply as noted with contract requirements.
D --	Will be returned by separate correspondence.	G --	Other (Specify)

10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

CONTRACT NO.

SUBMITTAL FORM, Jan 96

SUBMITTAL REGISTER										CONTRACT NO.							
TITLE AND LOCATION Crookston Stage 1				CONTRACTOR													
T R A N S M I T T A L S E C T I O N	C A T E G O R Y	P A R T S / A S S E M B L Y	D E S C R I P T I O N	G O V E R N O R S I A F I E C A R T E V O W N E R	CONTRACTOR: SCHEDULE DATES		CONTRACTOR ACTION	APPROVING AUTHORITY			REMARKS						
					DATE FWD TO APPR AUTH/	DATE RCD TO OTHER FROM		DATE FWD TO APPR AUTH/	DATE RCD TO OTHER FROM	DATE OF ACTION		DATE OF ACTION					
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
			SD-03 Product Data														
			Geotextile Data		FIO												
			SD-06 Test Reports		FIO												
			Geotextile Test Results		FIO												
			SD-07 Certificates		FIO												
			Geotextile		FIO												
			SD-01 Preconstruction Submittals		G GT												
			Material Sources		G GT												
			SD-06 Test Reports		FIO												
			Gradation Test		FIO												
			SD-07 Certificates		FIO												
			Certified Weight Scale Tickets		FIO												
			SD-01 Preconstruction Submittals		FIO												
			Manufacturers Instructions		FIO												
			Shop Drawings		G STR												
			SD-03 Product Data		FIO												
			Placing Pipe		FIO												
			SD-07 Certificates		FIO												
			Pipeline Testing		FIO												
			SD-01 Preconstruction Submittals		FIO												
			Aggregate Sources		FIO												
			SD-01 Preconstruction Submittals		FIO												
			Experience for Native Grasses		FIO												
			Erosion Control Matting Plan		G GEN												
			SD-03 Product Data		FIO												
			Manufacturer's Literature		FIO												

CONTRACT NO.

SUBMITTAL FORM, Jan 96  
PREVIOUS EDITION IS OBSOLETE  
PAGE 3 OF 3 PAGES

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01355

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 DEFINITIONS
  - 1.2.1 Environmental Pollution and Damage
  - 1.2.2 Environmental Protection
  - 1.2.3 Contractor Generated Hazardous Waste
  - 1.2.4 Land Application for Discharge Water
  - 1.2.5 Pesticide
  - 1.2.6 Pests
  - 1.2.7 Surface Discharge
  - 1.2.8 Waters of the United States
  - 1.2.9 Wetlands
- 1.3 GENERAL REQUIREMENTS
- 1.4 SUBCONTRACTORS
- 1.5 PAYMENT
- 1.6 SUBMITTALS
- 1.7 ENVIRONMENTAL PROTECTION PLAN
  - 1.7.1 Compliance
  - 1.7.2 Contents
  - 1.7.3 Appendix
- 1.8 PROTECTION FEATURES
- 1.9 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS
- 1.10 NOTIFICATION

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

- 3.1 PERMITS
- 3.2 LAND RESOURCES
  - 3.2.1 Work Area Limits
  - 3.2.2 Landscape
  - 3.2.3 Erosion and Sediment Controls
  - 3.2.4 Contractor Facilities and Work Areas
- 3.3 WATER RESOURCES
  - 3.3.1 Cofferdams, Diversions, and Dewatering Operations
  - 3.3.2 Stream Crossings
  - 3.3.3 Wetlands
- 3.4 AIR RESOURCES

- 3.4.1 Particulates
- 3.4.2 Odors
- 3.4.3 Sound Intrusions
- 3.5 CHEMICAL MATERIALS MANAGEMENT AND WASTE DISPOSAL
  - 3.5.1 Solid Wastes
  - 3.5.2 Chemicals and Chemical Wastes
  - 3.5.3 Contractor Generated Hazardous Wastes/Excess Hazardous Materials
  - 3.5.4 Fuel and Lubricants
  - 3.5.5 Waste Water
- 3.6 RECYCLING AND WASTE MINIMIZATION
- 3.7 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES
- 3.8 BIOLOGICAL RESOURCES
- 3.9 PESTICIDES
  - 3.9.1 Pesticide Delivery and Storage
  - 3.9.2 Qualifications
  - 3.9.3 Pesticide Handling Requirements
  - 3.9.4 Application
- 3.10 PREVIOUSLY USED EQUIPMENT
- 3.11 MAINTENANCE OF POLLUTION FACILITIES
- 3.12 TRAINING OF CONTRACTOR PERSONNEL
- 3.13 POST CONSTRUCTION CLEANUP

-- End of Section Table of Contents --



## SECTION 01355

### ENVIRONMENTAL PROTECTION

#### PART 1 GENERAL

##### 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

##### CODE OF FEDERAL REGULATIONS (CFR)

33 CFR 328	Definitions
40 CFR 68	Chemical Accident Prevention Provisions
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 279	Standards for the Management of Used Oil
40 CFR 302	Designation, Reportable Quantities, and Notification
40 CFR 355	Emergency Planning and Notification
49 CFR 171 - 178	Hazardous Materials Regulations

##### ENGINEERING MANUALS (EM)

EM 385-1-1	(1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual
------------	---

##### US ARMY CORPS OF ENGINEERS TECHNICAL REPORT

WETLAND MANUAL	Corps of Engineers Wetlands Delineation Manual Technical Report Y-87-1
----------------	--

##### 1.2 DEFINITIONS

###### 1.2.1 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical,

or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally and/or historically.

#### 1.2.2 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

#### 1.2.3 Contractor Generated Hazardous Waste

Contractor generated hazardous waste means materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e. methyl ethyl ketone, toluene etc.), waste thinners, excess paints, excess solvents, waste solvents, and excess pesticides, and contaminated pesticide equipment rinse water.

#### 1.2.4 Land Application for Discharge Water

The term "Land Application" for discharge water implies that the Contractor shall discharge water at a rate which allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage areas, or discharge into the "waters of the United States" shall occur. Land Application shall be in compliance with all applicable Federal, State, and local laws and regulations.

#### 1.2.5 Pesticide

Pesticide is defined as any substance or mixture of substances intended for preventing, destroying, repelling, or mitigating any pest, or intended for use as a plant regulator, defoliant or desiccant.

#### 1.2.6 Pests

The term "pests" means arthropods, birds, rodents, nematodes, fungi, bacteria, viruses, algae, snails, marine borers, snakes, weeds and other organisms (except for human or animal disease-causing organisms) that adversely affect readiness, military operations, or the well-being of personnel and animals; attack or damage real property, supplies, equipment, or vegetation; or are otherwise undesirable.

#### 1.2.7 Surface Discharge

The term "Surface Discharge" implies that the water is discharged with possible sheeting action and subsequent soil erosion may occur. Waters

that are surface discharged may terminate in drainage ditches, storm sewers, creeks, and/or "waters of the United States" and would require a permit to discharge water from the governing agency.

#### 1.2.8 Waters of the United States

All waters which are under the jurisdiction of the Clean Water Act, as defined in 33 CFR 328.

#### 1.2.9 Wetlands

Wetlands means those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, and bogs. Official determination of whether or not an area is classified as a wetland must be done in accordance with WETLAND MANUAL.

### 1.3 GENERAL REQUIREMENTS

The Contractor shall minimize environmental pollution and damage that may occur as the result of construction operations. The environmental resources within the project boundaries and those affected outside the limits of permanent work shall be protected during the entire duration of this contract. The Contractor shall comply with all applicable environmental Federal, State, and local laws and regulations. The Contractor shall be responsible for any delays resulting from failure to comply with environmental laws and regulations.

#### 1.4 SUBCONTRACTORS

The Contractor shall ensure compliance with this section by subcontractors.

#### 1.5 PAYMENT

No separate payment will be made for work covered under this section. The Contractor shall be responsible for payment of fees associated with environmental permits, application, and/or notices obtained by the Contractor. All costs associated with this section shall be included in the contract price. The Contractor shall be responsible for payment of all fines/fees for violation or non-compliance with Federal, State, Regional and local laws and regulations.

#### 1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Environmental Protection Plan; G,ENV

The environmental protection plan.

#### 1.7 ENVIRONMENTAL PROTECTION PLAN

Prior to commencing construction activities or delivery of materials to the site, the Contractor shall submit an Environmental Protection Plan for review and approval by the Contracting Officer. The purpose of the Environmental Protection Plan is to present a comprehensive overview of known or potential environmental issues which the Contractor must address during construction. Issues of concern shall be defined within the Environmental Protection Plan as outlined in this section. The Contractor shall address each topic at a level of detail commensurate with the environmental issue and required construction task(s). Topics or issues which are not identified in this section, but which the Contractor considers necessary, shall be identified and discussed after those items formally identified in this section. Prior to submittal of the Environmental Protection Plan, the Contractor shall meet with the Contracting Officer for the purpose of discussing the implementation of the initial Environmental Protection Plan; possible subsequent additions and revisions to the plan including any reporting requirements; and methods for administration of the Contractor's Environmental Plans. The Environmental Protection Plan shall be current and maintained onsite by the Contractor.

##### 1.7.1 Compliance

No requirement in this Section shall be construed as relieving the Contractor of any applicable Federal, State, and local environmental protection laws and regulations. During Construction, the Contractor shall be responsible for identifying, implementing, and submitting for approval any additional requirements to be included in the Environmental Protection Plan.

##### 1.7.2 Contents

The environmental protection plan shall include, but shall not be limited to, the following:

- a. Name(s) of person(s) within the Contractor's organization who is(are) responsible for ensuring adherence to the Environmental Protection Plan.
- b. Name(s) and qualifications of person(s) responsible for manifesting hazardous waste to be removed from the site, if applicable.
- c. Name(s) and qualifications of person(s) responsible for training the Contractor's environmental protection personnel.
- d. Description of the Contractor's environmental protection personnel training program.
- e. An erosion and sediment control plan which identifies the type and location of the erosion and sediment controls to be provided. The plan

shall include monitoring and reporting requirements to assure that the control measures are in compliance with the erosion and sediment control plan, Federal, State, and local laws and regulations. A Storm Water Pollution Prevention Plan (SWPPP) may be substituted for this plan.

f. Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on the site.

g. Traffic control plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather. Plan shall include measures to minimize the amount of mud transported onto paved public roads by vehicles or runoff.

h. Work area plan showing the proposed activity in each portion of the area and identifying the areas of limited use or nonuse. Plan should include measures for marking the limits of use areas including methods for protection of features to be preserved within authorized work areas.

i. Drawing showing the location of borrow areas.

j. The Spill Control plan shall include the procedures, instructions, and reports to be used in the event of an unforeseen spill of a substance regulated by 40 CFR 68, 40 CFR 302, 40 CFR 355, and/or regulated under State or Local laws and regulations. The Spill Control Plan supplements the requirements of EM 385-1-1. This plan shall include as a minimum:

1. The name of the individual who will report any spills or hazardous substance releases and who will follow up with complete documentation. This individual shall immediately notify the Contracting Officer, and the local Fire Department for flammable materials, in addition to the legally required Federal, State, and local reporting channels (including the National Response Center 1-800-424-8802) if a reportable quantity is released to the environment. The plan shall contain a list of the required reporting channels and telephone numbers.

2. The name and qualifications of the individual who will be responsible for implementing and supervising the containment and cleanup.

3. Training requirements for Contractor's personnel and methods of accomplishing the training.

4. A list of materials and equipment to be immediately available at the job site, tailored to cleanup work of the potential hazard(s) identified.

5. The names and locations of suppliers of containment materials and locations of additional fuel oil recovery, cleanup,

restoration, and material-placement equipment available in case of an unforeseen spill emergency.

6. The methods and procedures to be used for expeditious contaminant cleanup.

k. A non-hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris. The plan shall include schedules for disposal. The Contractor shall identify any subcontractors responsible for the transportation and disposal of solid waste. Licenses or permits shall be submitted for solid waste disposal sites that are not a commercial operating facility. Evidence of the disposal facility's acceptance of the solid waste shall be attached to this plan during the construction.

l. A recycling and solid waste minimization plan with a list of measures to reduce consumption of energy and natural resources. The plan shall detail the Contractor's actions to comply with and to participate in Federal, State, Regional, and local government sponsored recycling programs to reduce the volume of solid waste at the source.

m. An air pollution control plan detailing provisions to assure that dust, debris, materials, trash, etc., do not become air borne and travel off the project site.

n. A contaminant prevention plan that: identifies potentially hazardous substances to be used on the job site; identifies the intended actions to prevent introduction of such materials into the air, water, or ground; and details provisions for compliance with Federal, State, and local laws and regulations for storage and handling of these materials. In accordance with EM 385-1-1, a copy of the Material Safety Data Sheets (MSDS) and the maximum quantity of each hazardous material to be on site at any given time shall be included in the contaminant prevention plan. As new hazardous materials are brought on site or removed from the site, the plan shall be updated.

o. A waste water management plan that identifies the methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines. If a settling/retention pond is required, the plan shall include the design of the pond including drawings, removal plan, and testing requirements for possible pollutants. If land application will be the method of disposal for the waste water, the plan shall include a sketch showing the location for land application along with a description of the pretreatment methods to be implemented. If surface discharge will be the method of disposal, a copy of the permit and associated documents shall be included as an attachment prior to discharging the waste water. If disposal is to a sanitary sewer, the plan shall include documentation that the Waste Water Treatment Plant Operator has approved the flow rate, volume, and type of discharge.

p. A historical, archaeological, cultural resources biological

resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands known to be on the project site: and/or identifies procedures to be followed if historical archaeological, cultural resources, biological resources and wetlands not previously known to be onsite or in the area are discovered during construction. The plan shall include methods to assure the protection of known or discovered resources and shall identify lines of communication between Contractor personnel and the Contracting Officer.

q. A pesticide treatment plan shall be included and updated, as information becomes available. The plan shall include: sequence of treatment, dates, times, locations, pesticide trade name, EPA registration numbers, authorized uses, chemical composition, formulation, original and applied concentration, application rates of active ingredient (i.e. pounds of active ingredient applied), equipment used for application and calibration of equipment. The Contractor is responsible for Federal, State, Regional and Local pest management record keeping and reporting requirements.

#### 1.7.3 Appendix

Copies of all environmental permits, permit application packages, approvals to construct, notifications, certifications, reports, and termination documents shall be attached, as an appendix, to the Environmental Protection Plan.

#### 1.8 PROTECTION FEATURES

This paragraph supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. Prior to start of any onsite construction activities, the Contractor and the Contracting Officer shall make a joint condition survey. Immediately following the survey, the Contractor shall prepare a brief report including a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. This survey report shall be signed by both the Contractor and the Contracting Officer upon mutual agreement as to its accuracy and completeness. The Contractor shall protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference which their preservation may cause to the Contractor's work under the contract.

#### 1.9 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS

Any deviations, requested by the Contractor, from the drawings, plans and specifications which may have an environmental impact will be subject to approval by the Contracting Officer and may require an extended review, processing, and approval time. The Contracting Officer reserves the right to disapprove alternate methods, even if they are more cost effective, if the Contracting Officer determines that the proposed alternate method will

have an adverse environmental impact.

#### 1.10 NOTIFICATION

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with Federal, State or local environmental laws or regulations, permits, and other elements of the Contractor's Environmental Protection plan. The Contractor shall, after receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping (suspending) all or part of the work until satisfactory corrective action has been taken. No time extensions shall be granted or equitable adjustments allowed to the Contractor for any such suspensions. This is in addition to any other actions the Contracting Officer may take under the contract, or in accordance with the Federal Acquisition Regulation or Federal Law.

#### PART 2 PRODUCTS (NOT USED)

#### PART 3 EXECUTION

##### 3.1 PERMITS

Permits obtained by the Government related to the work of this contract are attached in SECTION 00830: ATTACHMENTS, or referenced in SECTION 01000: GENERAL. The Contractor is responsible for obtaining all applicable permits or licenses(those not obtained by the Government). The Contractor shall be responsible for implementing the terms and requirements of the permits held by the Contractor or the Government. A copy of permits referenced in SECTION 01000: GENERAL are available for inspection in the Office of the District Engineer, Army Corps of Engineers Centre, 190 Fifth Street East, St. Paul, Minnesota 55101-1638.

##### 3.2 LAND RESOURCES

The Contractor shall confine all activities to areas defined by the drawings and specifications. Prior to the beginning of any construction, the Contractor shall identify any land resources to be preserved within the work area. Except in areas indicated on the drawings or specified to be cleared, the Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, topsoil, and land forms without approval. No ropes, cables, or guys shall be fastened to or attached to any trees for anchorage unless specifically authorized. The Contractor shall provide effective protection for land and vegetation resources at all times as defined in the following subparagraphs. Stone, soil, or other materials displaced into uncleared areas shall be removed by the Contractor.

###### 3.2.1 Work Area Limits

Prior to commencing construction activities, the Contractor shall mark the areas that need not be disturbed under this contract. Isolated areas



within the general work area which are not to be disturbed shall be marked or fenced. Monuments and markers shall be protected before construction operations commence. Where construction operations are to be conducted during darkness, any markers shall be visible in the dark. The Contractor's personnel shall be knowledgeable of the purpose for marking and/or protecting particular objects.

#### 3.2.2 Landscape

Trees, shrubs, vines, grasses, land forms and other landscape features indicated and defined on the drawings to be preserved shall be clearly identified by marking, fencing, or wrapping with boards, or any other approved techniques. The Contractor shall restore landscape features damaged or destroyed during construction operations outside the limits of the approved work area.

#### 3.2.3 Erosion and Sediment Controls

The Contractor shall be responsible for providing erosion and sediment control measures in accordance with Federal, State, and local laws and regulations. The erosion and sediment controls selected and maintained by the Contractor shall be such that water quality standards are not violated as a result of the Contractor's construction activities. The area of bare soil exposed at any one time by construction operations should be kept to a minimum. The Contractor shall construct or install temporary and permanent erosion and sediment control best management practices (BMPs). BMPs may include, but not be limited to, vegetation cover, stream bank stabilization, slope stabilization, silt fences, construction of terraces, interceptor channels, sediment traps, inlet and outfall protection, diversion channels, and sedimentation basins. Any temporary measures shall be removed after the area has been stabilized.

#### 3.2.4 Contractor Facilities and Work Areas

The Contractor's field offices, staging areas, stockpile storage, and temporary buildings shall be placed in areas designated on the drawings or as directed by the Contracting Officer. Temporary movement or relocation of Contractor facilities shall be made only when approved. Erosion and sediment controls shall be provided for on-site borrow and spoil areas to prevent sediment from entering nearby waters. Temporary excavation and embankments for plant and/or work areas shall be controlled to protect adjacent areas.

### 3.3 WATER RESOURCES

The Contractor shall monitor construction activities to prevent pollution of surface and ground waters. Toxic or hazardous chemicals shall not be applied to soil or vegetation unless otherwise indicated. All water areas affected by construction activities shall be monitored by the Contractor. For construction activities immediately adjacent to impaired surface waters, the Contractor shall be capable of quantifying sediment or pollutant loading to that surface water when required by State or Federally issued Clean Water Act permits.

#### 3.3.1 Cofferdams, Diversions, and Dewatering Operations

Construction operations for dewatering, water return for hydraulic dredging, removal of cofferdams, tailrace excavation, and tunnel closure shall be controlled at all times to maintain compliance with existing State water quality standards and designated uses of the surface water body. The Contractor shall plan its operations and perform all work necessary to minimize adverse impact, such as water turbidity, on the habitat for wildlife and on water quality for downstream use.

#### 3.3.2 Stream Crossings

Stream crossings shall allow movement of materials or equipment without violating water pollution control standards of the Federal, State, and local governments.

#### 3.3.3 Wetlands

The Contractor shall not enter, disturb, destroy, or allow discharge of contaminants into any wetlands, unless authorized herein. The Contractor shall be responsible for the protection of wetlands shown on the drawings in accordance with paragraph ENVIRONMENTAL PERMITS, REVIEWS, AND APPROVALS.

Authorization to enter specific wetlands identified shall not relieve the Contractor from any obligation to protect other wetlands within, adjacent to, or in the vicinity of the construction site and associated boundaries.

#### 3.4 AIR RESOURCES

Equipment operation, activities, or processes performed by the Contractor shall be in accordance with all Federal and State air emission and performance laws and standards.

##### 3.4.1 Particulates

Dust particles; aerosols and gaseous by-products from construction activities; and processing and preparation of materials, such as from asphaltic batch plants; shall be controlled at all times, including weekends, holidays and hours when work is not in progress. The Contractor shall maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates which would cause the Federal, State, and local air pollution standards to be exceeded or which would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp at all times. The Contractor must have sufficient, competent equipment available to accomplish these tasks. Particulate control shall be performed as the work proceeds and whenever a particulate nuisance or hazard occurs. The Contractor shall comply with all State and local visibility regulations.

##### 3.4.2 Odors

Odors from construction activities shall be controlled at all times. The odors shall not cause a health hazard and shall be in compliance with State regulations and/or local ordinances.

#### 3.4.3 Sound Intrusions

The Contractor shall keep construction activities under surveillance and control to minimize environment damage by noise. The Contractor shall comply with state rules.

### 3.5 CHEMICAL MATERIALS MANAGEMENT AND WASTE DISPOSAL

Disposal of wastes shall be as directed below, unless otherwise specified in other sections and/or shown on the drawings.

#### 3.5.1 Solid Wastes

Solid wastes (excluding dredge material and clearing debris) shall be placed in containers which are emptied on a regular schedule. Handling, storage, and disposal shall be conducted to prevent contamination. Segregation measures shall be employed so that no hazardous or toxic waste will become co-mingled with solid waste. The Contractor shall transport solid waste off Government property and dispose of it in compliance with Federal, State, and local requirements for solid waste disposal. A Subtitle D RCRA permitted landfill shall be the minimum acceptable off-site solid waste disposal option. The Contractor shall verify that the selected transporters and disposal facilities have the necessary permits and licenses to operate.

#### 3.5.2 Chemicals and Chemical Wastes

Chemicals shall be dispensed ensuring no spillage to the ground or water. Periodic inspections of dispensing areas to identify leakage and initiate corrective action shall be performed. Chemical waste shall be collected in corrosion resistant, compatible containers. Collection drums shall be monitored and removed to a staging or storage area when contents are within 6 inches of the top. Wastes shall be classified, managed, stored, and disposed of in accordance with Federal, State, and local laws and regulations.

#### 3.5.3 Contractor Generated Hazardous Wastes/Excess Hazardous Materials

Hazardous wastes are defined in 40 CFR 261, or are as defined by applicable State and local regulations. Hazardous materials are defined in 49 CFR 171 - 178. The Contractor shall, at a minimum, manage and store hazardous waste in compliance with 40 CFR 262. The Contractor shall take sufficient measures to prevent spillage of hazardous and toxic materials during dispensing. The Contractor shall segregate hazardous waste from other materials and wastes, shall protect it from the weather by placing it in a safe covered location, and shall take precautionary measures such as berming or other appropriate measures against accidental spillage. The Contractor shall be responsible for storage, describing, packaging, labeling, marking, and placarding of hazardous waste and hazardous material in accordance with 49 CFR 171 - 178, State, and local laws and regulations.

The Contractor shall transport Contractor generated hazardous waste off Government property in accordance with the Environmental Protection Agency and the Department of Transportation laws and regulations. The Contractor shall dispose of hazardous waste in compliance with Federal, State and local laws and regulations. Spills of hazardous or toxic materials shall be immediately reported to the Contracting Officer. Cleanup and cleanup costs due to spills shall be the Contractor's responsibility. The disposition of Contractor generated hazardous waste and excess hazardous materials are the Contractor's responsibility.

#### 3.5.4 Fuel and Lubricants

Storage, fueling and lubrication of equipment and motor vehicles shall be conducted in a manner that affords the maximum protection against spill and evaporation. Fuel, lubricants and oil shall be managed and stored in accordance with all Federal, State, Regional, and local laws and regulations. Used lubricants and used oil to be discarded shall be stored in marked corrosion-resistant containers and recycled or disposed in accordance with 40 CFR 279, State, and local laws and regulations.

#### 3.5.5 Waste Water

Waste water from construction activities, such as onsite material processing, concrete curing, foundation and concrete clean-up, water used in concrete trucks, forms, etc. shall not be allowed to enter water ways.

#### 3.6 RECYCLING AND WASTE MINIMIZATION

The Contractor shall participate in State and local government sponsored recycling programs.

#### 3.7 HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES

Existing historical, archaeological, and cultural resources within the Contractor's work area are shown on the drawings, or will be designated by the Contracting Officer, if any have been identified. The Contractor shall protect these resources and shall be responsible for their preservation during the life of the Contract. If during excavation or other construction activities any previously unidentified or unanticipated historical, archaeological, and cultural resources are discovered or found, all activities that may damage or alter such resources shall be temporarily suspended. Resources covered by this paragraph include but are not limited to: any human skeletal remains or burials; artifacts; shell, midden, bone, charcoal, or other deposits; rock or coral alignments, pavings, wall, or other constructed features; and any indication of agricultural or other human activities. Upon such discovery or find, the Contractor shall immediately notify the Contracting Officer so that the appropriate authorities may be notified and a determination made as to their significance and what, if any, special disposition of the finds should be made. The Contractor shall cease all activities that may result in impact to or the destruction of these resources. The Contractor shall secure the area and prevent employees or other persons from trespassing on, removing, or otherwise disturbing such resources.

### 3.8 BIOLOGICAL RESOURCES

The Contractor shall minimize interference with, disturbance to, and damage to fish, wildlife, and plants including their habitat. The Contractor shall be responsible for the protection of threatened and endangered animal and plant species including their habitat in accordance with Federal, State, Regional, and local laws and regulations.

### 3.9 PESTICIDES

#### 3.9.1 Pesticide Delivery and Storage

Pesticides shall be delivered to the site in the original, unopened containers bearing legible labels indicating the EPA registration number and the manufacturer's registered uses. Pesticides shall be stored according to manufacturer's instructions and under lock and key when unattended.

#### 3.9.2 Qualifications

For the application of pesticides, the Contractor shall use the services of a subcontractor whose principal business is pest control. The subcontractor shall be licensed and certified in the state where the work is to be performed.

#### 3.9.3 Pesticide Handling Requirements

The Contractor shall formulate, treat with, and dispose of pesticides and associated containers in accordance with label directions and shall use the clothing and personal protective equipment specified on the labeling for use during all phases of the application. Material Safety Data Sheets (MSDS) shall be available for all pesticide products.

#### 3.9.4 Application

Pesticides shall be applied by a State Certified Pesticide Applicator in accordance with EPA label restrictions and recommendation. The Certified Applicator shall wear clothing and personal protective equipment as specified on the pesticide label. Water used for formulating shall only come from locations designated by the Contracting Officer. The Contractor shall not allow the equipment to overflow. Prior to application of pesticide, all equipment shall be inspected for leaks, clogging, wear, or damage and shall be repaired prior to being used.

### 3.10 PREVIOUSLY USED EQUIPMENT

The Contractor shall clean all previously used construction equipment prior to bringing it onto the project site. The Contractor shall ensure that the equipment is free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. The Contractor shall consult with the USDA jurisdictional office for additional cleaning requirements.

### 3.11 MAINTENANCE OF POLLUTION FACILITIES

The Contractor shall maintain permanent and temporary pollution control facilities and devices for the duration of the contract or for that length of time construction activities create the particular pollutant.

### 3.12 TRAINING OF CONTRACTOR PERSONNEL

The Contractor's personnel shall be trained in all phases of environmental protection and pollution control. The Contractor shall conduct environmental protection/pollution control meetings for all Contractor personnel prior to commencing construction activities. Additional meetings shall be conducted for new personnel and when site conditions change. The training and meeting agenda shall include: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, wetlands, and endangered species and their habitat that are known to be in the area.

### 3.13 POST CONSTRUCTION CLEANUP

The Contractor shall clean up all areas used for construction in accordance with Contract Clause: "Cleaning Up". The Contractor shall, unless otherwise instructed in writing by the Contracting Officer, obliterate all signs of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. The disturbed area shall be graded, filled and the entire area seeded unless otherwise indicated.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01451

CONTRACTOR QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

3.2 QUALITY CONTROL PLAN

3.2.1 General

3.2.2 Content of the CQC Plan

3.2.3 Acceptance of Plan

3.2.4 Notification of Changes

3.3 COORDINATION MEETING

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

3.4.2 CQC System Manager

3.4.3 Additional Requirement

3.4.4 Organizational Changes

3.5 SUBMITTALS AND DELIVERABLES

3.6 CONTROL

3.6.1 Preparatory Phase

3.6.2 Initial Phase

3.6.3 Follow-up Phase

3.6.4 Additional Preparatory and Initial Phases

3.7 TESTS

3.7.1 Testing Procedure

3.7.2 Testing Laboratories

3.7.2.1 Capability Check

3.7.2.2 Capability Recheck

3.7.3 Onsite Laboratory

3.7.4 Furnishing or Transportation of Samples for Testing

3.8 COMPLETION INSPECTION

3.8.1 Punch-Out Inspection

3.8.2 Pre-Final Inspection

3.8.3 Final Acceptance Inspection

3.9 DOCUMENTATION

3.10 SAMPLE FORMS

3.11 NOTIFICATION OF NONCOMPLIANCE

3.12 IMPLEMENTATION OF GOVERNMENT RESIDENT MANAGEMENT SYSTEM FOR  
CONTRACTOR QUALITY CONTROL OF CONTRACT

3.12.1 Revisions  
3.12.2 Pay Activity

-- End of Section Table of Contents --



## SECTION 01451

### CONTRACTOR QUALITY CONTROL

#### PART 1 GENERAL

##### 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

#### AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740	(1999) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E 329	(1998) Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

#### PART 2 PRODUCTS (Not Applicable)

#### PART 3 EXECUTION

##### 3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

##### 3.2 QUALITY CONTROL PLAN

### 3.2.1 General

The Contractor shall furnish for review by the Government, not later than 15 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, tests, records, and forms to be used. The Government will consider an interim plan for the first 30 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

### 3.2.2 Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project superintendent or someone higher in the Contractor's organization.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.
- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities will be approved by the Contracting Officer.)
- f. Procedures for tracking preparatory, initial, and follow-up

control phases and control, verification, and acceptance tests including documentation.

- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

### 3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

### 3.2.4 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

### 3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted for review a minimum of 10 calendar days prior to the Coordination Meeting.

During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

### 3.4 QUALITY CONTROL ORGANIZATION

#### 3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure safety and contract compliance. The Safety and Health Manager shall receive direction and authority from the CQC System Manager and shall serve as a member of the CQC staff. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, shop drawing submittals, schedules and all other project documentation shall be maintained at the site at all times, except as otherwise acceptable to the Contracting Officer.

#### 3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a graduate engineer, or a graduate of construction management, with a minimum of 5 years experience in related duties on construction similar to this contract, or a person with a minimum of 15 years experience in related duties on construction work. This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned as System Manager but may have duties as project superintendent in addition to quality control. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

#### 3.4.3 Additional Requirement

In addition to the above qualifications, the CQC System Manager shall have completed the course entitled "Construction Quality Management For Contractors". This course is periodically offered through the Government in the Minneapolis - St. Paul, Minnesota metropolitan area.

#### 3.4.4 Organizational Changes

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

### 3.5 SUBMITTALS AND DELIVERABLES

Submittals, if needed, shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for

certifying that all submittals and deliverables are in compliance with the contract requirements.

### 3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

#### 3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.
- b. A review of the contract drawings.
- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. Discussion of the initial control phase.

- k. The Government shall be notified at least 48 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

#### 3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 48 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

#### 3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

#### 3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

### 3.7 TESTS

#### 3.7.1 Testing Procedure

The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements. Upon request, the Contractor shall furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a testing laboratory meeting the requirements listed under PARAGRAPH: CAPABILITY CHECK, or establish a testing laboratory at the project site meeting those requirements. The Contractor shall perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.
- e. Results of all tests taken, both passing and failing tests, shall be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test shall be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an offsite or commercial test facility shall be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.

#### 3.7.2 Testing Laboratories

##### 3.7.2.1 Capability Check

The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques. Laboratories utilized for testing soils,

concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329. The Contractor shall submit a Quality Management Manual meeting the requirements of ASTM D 3740 and ASTM E 329 for each laboratory to be used, including on-site project laboratories.

#### 3.7.2.2 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will be assessed a charge of \$1000.00 to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the contract amount due the Contractor.

#### 3.7.3 Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

#### 3.7.4 Furnishing or Transportation of Samples for Testing

Costs incidental to the transportation of samples or materials shall be borne by the Contractor. Samples of materials for test verification and acceptance testing by the Government shall be delivered to the Contracting Officer. Coordination for each specific test, exact delivery location, and dates will be made with the Contracting Officer.

### 3.8 COMPLETION INSPECTION

#### 3.8.1 Punch-Out Inspection

Near the end of the work, or any increment of the work established by a time stated in the Special Clause, "Commencement, Prosecution, and Completion of Work", or by the specifications, the CQC Manager shall conduct an inspection of the work. A punch list of items which do not conform to the approved drawings and specifications shall be prepared and included in the CQC documentation, as required by paragraph DOCUMENTATION. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected.

Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

#### 3.8.2 Pre-Final Inspection

The Government will perform the pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or



any particular increment of the work if the project is divided into increments by separate completion dates.

### 3.8.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance the final acceptance inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

### 3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Off-site surveillance activities, including actions taken.

- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

### 3.10 SAMPLE FORMS

The following sample forms are enclosed at the end of this section:

- a. Construction Quality Control Management Report
- b. CQC Report
- c. Preparatory Phase Checklist
- d. Initial Phase Checklist

### 3.11 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

### 3.12 IMPLEMENTATION OF GOVERNMENT RESIDENT MANAGEMENT SYSTEM FOR CONTRACTOR QUALITY CONTROL OF CONTRACT

The Contractor shall utilize the Contractor Quality Control (CQC) module of

the Resident Management System (RMS). The RMS-CQC module is a computer program which is executable on IBM compatible computers with 80386, 80486 and Pentium processors. This module includes a daily CQC reporting form which must be used. The module shall be completed to the satisfaction of the Contracting Officer prior to any contract payment and shall be updated as required. The Contractor shall complete module elements including:

- Prime Contractor staffing
- Subcontractor information, including name, address, trade, and point of contact
- Submittal information, including description, activity number, review period, expected procurement period
- Quality control testing
- Definable features of work
- Installed property listing
- Transfer property listing
- Pay activity and activity information
- Planned cumulative progress earnings
- Scheduled employee education required by the specifications
- Insurance expiration dates

#### 3.12.1 Revisions

The Contractor shall acknowledge receipt of Government comments relating to the RMS-CQC module by specific number reference on his Daily CQC report. The daily CQC report shall also report when corrections are implemented.

#### 3.12.2 Pay Activity

The sum of all pay activity values shall equal the contract amount. Bid items may include multiple activities, but activities shall only be assigned to one bid item.

-- End of Section --



CQC Report

1. Work performed today: (Indicate location and description of work performed by prime and/or subcontractors by letter in table above).

---

---

---

---

---

---

---

---

2. Results of control activities: (Indicate whether P - Preparatory, I - Initial, or F - Follow-up Phase. When a P or I meeting is conducted, complete attachment 1-A or 1-B, respectively. When network analysis system is used, identify work by use of I-J numbers)

---

---

---

---

---

---

---

---

3. Test performed as required by plans and/or specifications:

---

---

---

---

---

---

---

---

4. Material received:

---

---

---

---

---

---

---

---

CQC Report (Cont'd)

5. Submittals Reviewed:

(a) Submittal No.	(b) Spec/Plan Reference	(c) By Whom	(d) Action
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

6. Off-site surveillance activities, including action taken:

---

---

---

---

---

---

---

---

7. Job safety: (Report violations; Corrective instructions given; Corrective actions taken).

---

---

---

---

---

---

---

---

8. Remarks: (Instructions received or given. Conflict(s) in Plans and/or Specifications)

---

---

---

---

---

---

---

---

Contractor's Verification: On behalf of the Contractor, I certify this report is complete and correct, and all materials and equipment used and work performed during this reporting period are in compliance with the contract plans and specifications, to the best of my knowledge, except as noted above.

\_\_\_\_\_  
CQC System Manager



PREPARATORY PHASE CHECKLIST

Contract No.: \_\_\_\_\_ Date: \_\_\_\_\_  
Definable Feature: \_\_\_\_\_ Spec Section: \_\_\_\_\_

Government Rep Notified \_\_\_\_\_ Hours in Advance Yes \_\_\_\_ No \_\_\_\_

I. Personnel Present.

	Name	Position	Company/Government
1.	_____	_____	_____
2.	_____	_____	_____
3.	_____	_____	_____
4.	_____	_____	_____
5.	_____	_____	_____
6.	_____	_____	_____
7.	_____	_____	_____

(List additional personnel on reverse side)

II. Submittals.

1. Review submittals and/or submittal log 4288. Have all submittals been approved? Yes \_\_\_\_ No \_\_\_\_

If No, what items have not been submitted?

a. \_\_\_\_\_  
b. \_\_\_\_\_  
c. \_\_\_\_\_  
2. Are all materials on hand? Yes \_\_\_\_ No \_\_\_\_  
a. \_\_\_\_\_  
b. \_\_\_\_\_  
c. \_\_\_\_\_

3. Check approved submittals against delivered material. (This should be done as material arrives).

Comments: \_\_\_\_\_

III. Material Storage.

Are materials stored properly? Yes \_\_\_\_ No \_\_\_\_

If No, what action is taken?



Preparatory Phase Checklist (Cont'd)

IV. Specifications.

1. Review each paragraph of specifications.

---

---

---

2. Discuss procedure for accomplishing the work.

---

---

---

---

---

3. Clarify any differences.

---

---

---

---

---

V. Preliminary Work.

Ensure preliminary work is correct.

If not, what action is taken? \_\_\_\_\_

---

VI. Testing.

1. Identify test to be performed, frequency, and by whom.

2. When required? \_\_\_\_\_

3. Where required? \_\_\_\_\_

4. Review Testing Plan. \_\_\_\_\_

5. Has test facilities been approved? \_\_\_\_\_

VII. Safety.

1. Review applicable portion of EM 385-1-1. \_\_\_\_\_

---

2. Activity Hazard Analysis approved? Yes \_\_\_\_\_ No \_\_\_\_\_

VIII. Corps of Engineers comments during meeting.

---

---

---

\_\_\_\_\_  
CQC System Manager

INITIAL PHASE CHECKLIST

Contract No.: \_\_\_\_\_ Date: \_\_\_\_\_

Definable Feature: \_\_\_\_\_

Government Rep Notified: \_\_\_\_\_ Hours in Advance Yes \_\_\_\_\_ No \_\_\_\_\_

I. Personnel Present:

	Name	Position	Company/Government
1.	_____	_____	_____
2.	_____	_____	_____
3.	_____	_____	_____
4.	_____	_____	_____
5.	_____	_____	_____
6.	_____	_____	_____

(List additional personnel on reverse side)

II. Identify full compliance with procedures identified at preparatory. Coordinate plans, specifications, and submittals.

Comments: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

III. Preliminary Work. Ensure preliminary work is complete and correct. If not, what action is taken? \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

IV. Establish Level of Workmanship.

1. Where is work located? \_\_\_\_\_
2. Is a sample panel required? Yes \_\_\_\_\_ No \_\_\_\_\_
3. Will the initial work be considered as a sample? Yes \_\_\_\_\_ No \_\_\_\_\_  
(If yes, maintain in present condition as long as possible).

V. Resolve any Differences.

Comments: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Review job conditions using EM 385-1-1 and job hazard analysis.

Comments: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
CQC System Manager



SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01500

TEMPORARY CONSTRUCTION FACILITIES

PART 1 GENERAL

- 1.1 SUBMITTALS
- 1.2 AVAILABILITY AND USE OF UTILITY SERVICES
  - 1.2.1 Temporary Electrical Facilities
  - 1.2.2 Sanitation
  - 1.2.3 Telephone
- 1.3 PROTECTION AND MAINTENANCE OF TRAFFIC
  - 1.3.1 Haul Roads
  - 1.3.2 Barricades
- 1.4 CONTRACTOR'S TEMPORARY FACILITIES
  - 1.4.1 Administrative Field Offices
  - 1.4.2 Staging Area
  - 1.4.3 Employee Parking
- 1.5 PLANT COMMUNICATION

PART 2 PRODUCTS

- 2.1 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN
  - 2.1.1 Bulletin Board
  - 2.1.2 Project and Safety Signs
- 2.2 GOVERNMENT FIELD OFFICE
  - 2.2.1 Location
  - 2.2.2 Construction
  - 2.2.3 Utilities.
  - 2.2.4 Furnishings
  - 2.2.5 Furniture
  - 2.2.6 Office Equipment
  - 2.2.7 Maintenance.

PART 3 EXECUTION

- 3.1 CLEANUP
- 3.2 RESTORATION OF STORAGE AREA

-- End of Section Table of Contents --

## SECTION 01500

### TEMPORARY CONSTRUCTION FACILITIES

#### PART 1 GENERAL

##### 1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

###### SD-02 Shop Drawings

###### Site Plan;

The Contractor shall prepare a site plan indicating the proposed location and dimensions of any area to be fenced and used by the Contractor, the number of trailers to be used, avenues of ingress/egress to the fenced area and details of the fence installation. Any areas which may have to be graveled to prevent the tracking of mud shall also be identified. The Contractor shall also indicate if the use of a supplemental or other staging area is desired.

###### Government Field Office;

The Contractor shall submit a preliminary plan and description of the mobile office facilities which it proposes to furnish prior to proceeding with procurement thereof.

##### 1.2 AVAILABILITY AND USE OF UTILITY SERVICES

###### 1.2.1 Temporary Electrical Facilities

The Contractor shall be responsible for coordination and costs for electrical power required for the Contractor's operations, including all costs for utility company hookup, installation/dismantling of transformers and distribution lines.

###### 1.2.2 Sanitation

The Contractor shall provide and maintain within the construction area field-type sanitary facilities in accordance with EM 385-1-1. These facilities shall include but not be limited to toilet, washing, and drinking water facilities.

###### 1.2.3 Telephone

The Contractor shall make arrangements and pay all costs for their telephone facilities desired. Government personnel will not take or deliver messages for the Contractor.

### 1.3 PROTECTION AND MAINTENANCE OF TRAFFIC

During construction the Contractor shall provide access and temporary relocated roads as necessary to maintain traffic. The Contractor shall maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment and the work, and the erection and maintenance of adequate warning, danger, and direction signs, shall be as required by the State and local authorities having jurisdiction. The traveling public shall be protected from damage to person and property. The Contractor's traffic on roads selected for hauling material to and from the site shall interfere as little as possible with public traffic. The Contractor shall investigate the adequacy of existing roads and the allowable load limit on these roads.

#### 1.3.1 Haul Roads

The Contractor shall, at its own expense, construct access and haul roads necessary for proper prosecution of the work under this contract. Haul roads shall be constructed with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic shall be avoided. The Contractor shall provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, shall be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and hauling roads shall be subject to approval by the Contracting Officer. Lighting shall be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations. Upon completion of the work, haul roads designated by the Contracting Officer shall be removed.

#### 1.3.2 Barricades

The Contractor shall erect and maintain temporary barricades to limit public access to hazardous areas. Such barricades shall be required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Barricades shall be securely placed, clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

### 1.4 CONTRACTOR'S TEMPORARY FACILITIES

#### 1.4.1 Administrative Field Offices

The Contractor shall provide and maintain administrative field office facilities within the construction area at the designated site. Government

office and warehouse facilities will not be available to the Contractor's personnel.

#### 1.4.2 Staging Area

The boundary limits of the grounds made available for the Contractor's use during the life of the contract are shown on the drawings as Work Limits. Trailers, materials, or equipment shall not be placed or stored outside the work limits.

#### 1.4.3 Employee Parking

Contractor employees shall park privately owned vehicles in an area designated by the Contracting Officer. This area will be within reasonable walking distance of the construction site. Contractor employee parking shall not interfere with existing and established parking requirements at the project site.

### 1.5 PLANT COMMUNICATION

Whenever the Contractor has the individual elements of its plant so located that operation by normal voice between these elements is not satisfactory, the Contractor shall install a satisfactory means of communication, such as telephone or other suitable devices. The devices shall be made available for use by Government personnel.

## PART 2 PRODUCTS

### 2.1 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN

#### 2.1.1 Bulletin Board

Immediately upon beginning of work, the Contractor shall provide a weatherproof glass-covered bulletin board not less than 36 by 48 inches in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained in the contract, Wage Rate Information poster, and other information approved by the Contracting Officer. The bulletin board shall be located at the project site in a conspicuous place easily accessible to all employees, as approved by the Contracting Officer. Legible copies of the aforementioned data shall be displayed until work is completed. Upon completion of work the bulletin board shall be removed by and remain the property of the Contractor.

#### 2.1.2 Project and Safety Signs

The Contractor shall furnish and erect a Project sign and a Safety sign in a location selected by the Contracting Officer at the project site within 15 days after receipt of the notice to proceed. The requirements for the signs and their content shall be as shown on the drawings at the end of this section. The data required by the safety sign shall be corrected daily. Signs shall be maintained throughout the construction period, and upon completion of the project, the signs shall be removed from the site. The PROJECT DESCRIPTION and PROJECT NAME shall be as follows:

PROJECT DESCRIPTION: FLOOD CONTROL - RED LAKE RIVER

PROJECT NAME: CROOKSTON - STAGE 1

2.2 GOVERNMENT FIELD OFFICE

The Contractor shall provide and maintain for the life of the contract an approved mobile office (mobile home style) meeting the following requirements as to space and facilities for the exclusive use of the government. The unit shall be ready for occupancy within 30 calendar days after notice to proceed. The unit shall provide a minimum of 200 square feet of floor area and shall include a private office, and a storage closet. The unit shall have two entrance doors. The remaining space is to be utilized as one large office, a toilet room, a chest of drawers and a storage area for coats, etc. The unit shall be provided with a toilet room consisting of a stool and lavatory and an electric heater. The unit interior headroom shall be no less than a nominal 8'-0".

2.2.1 Location

The Contractor shall locate the portable mobile home type field office at or near the Contractor's field office site at a location approved by the Contracting Officer. Four parking spaces shall be reserved for Government vehicles at the Government trailer.

2.2.2 Construction.

The Government field office shall be similar in quality and age as the Contractor's field office, if provided. Exterior and interior finishes shall be free from color fade, chipping, or peeling. The unit shall be set level on blocking, be provided with plywood skirting, and be anchored to the ground for protection against wind damage. Exterior doors shall be provided with screens and outside hasps for use with padlocks. The unit shall be electrically wired for fluorescent ceiling lighting fixtures and weather proof porch lights at each entrance door, along with switches, duplex convenience outlets, and a master switch and fuse box as required. The entire unit shall be adequately insulated with fiberglass insulation and vapor barrier. Dead air crawl space shall be properly ventilated. Heating and air conditioning facilities shall be provided to maintain an ambient inside temperature of 68 degrees F. The unit shall be weather proof, and furnished with a forced air type heating plant, either gas or oil with hot and cold air ducts adequate to supply even heat throughout the unit. Air conditioning shall be furnished with capacity as recommended by the manufacturer for the trailer size. A central air conditioning system shall be provided.

2.2.3 Utilities.

The Contractor shall be responsible for service fees in connection with electrical power and heating (natural gas or oil service). The Contractor shall also be responsible for service fees in connection with the water supply, sanitary waste system, and telephone as indicated below. When available, city water and sewer system connections are preferred.



- a. Sanitary Facilities. In the absence of a city sewer connection, holding tanks shall be provided. The lavatory shall discharge into an outside underground holding tank with a capacity of not less than 400 gallons and a vented drain. The contractor shall provide year-round pumping of the holding tank as required. Subject to approval, a serviced chemical toilet may be used.
- b. Potable Water. In the absence of a city water connection, a potable water storage tank of not less than 300 gallons capacity shall be furnished with adequate supply filling connections and screened vent, and shall be stainless steel or plastic with a drain cock of not less than ½ inch size. Upon completion of the job, the Contractor shall remove the underground holding tank and backfill the excavation. The Contractor shall provide potable water for the storage tank if service connections are not provided.
- c. Telephone. The Contractor shall be responsible for installation of telephone at the Government office. The telephone hook-up should be placed on a separate account from the Contractor's phone so that it can be transferred to the Government after installation. The Government will be responsible for the telephone service to the Government field office after installation.

#### 2.2.4 Furnishings.

The following furnishings shall be provided for the Government office:

- a. A hot and cold drinking water dispenser.
- b. Bulletin board, minimum size 6 square feet.
- c. A cabinet shall be supplied along a side wall with minimum nominal dimensions 2 feet wide, 3 feet high and 6 feet long. The cabinet shall include a finished wood or laminate counter. Two shelves, one above and one below the cabinet, shall be provided for storage.
- d. Sign. The contractor shall securely attach to the unit exterior and adjacent to the main entrance door, as approved, a 24 inch by 36 inch sign with the Corps of Engineers castle insignia with wording as specified.
- e. Stoop. A stoop with 8 inch risers and handrails shall be provided at each entrance door.
- f. Windows. All windows shall be provided with sash and security screens along with shades, blinds or similar features that allow for the complete coverage of the windows on the inside.
- g. Lavatory. A 5 by 24 inch metal shelf and 15 by 20 inch wood or metal framed plate glass mirror shall be provided above the lavatory.

#### 2.2.5 Furniture

Office furniture shall be coordinated with respect to style, color, and upholstery. The following furniture shall be provided:

- a. One desk either wood or steel, double pedestal type, top approximately 60 inches by 34 inches, with lock.
- b. One swivel armchairs with tilting seat and adjustable spring back.
- c. One filing cabinets, four-drawer legal size, with lock.
- d. One drafting table stool, non-tilting, rotary type with back and

circular footrest.

- e. One drafting table, metal and/or wood, 36 inches by 48 inches.
- f. One conference table, 3/4 inch thick by 72 inches long by 36 inches wide with solid core construction top.
- g. Eight chairs for conference table, either wood or steel construction, with cushioned seat and backrest.
- h. One rack for hanging full size drawings.

#### 2.2.6 Office Equipment

The following equipment shall be provided:

- a. One desk top facsimile (FAX) machine with modem BPS speeds of 9600, 7200, 4800, and 2400; an effective scanning width of 11.7 inches and line scanning density of 8 pels/mm horizontal and an effective scanning width of 7.7 inches and line scanning density of 3.85 lines/mm vertical. Initially supply four reams of paper (500 sheets per ream).
- b. One desk top copying machine with an indirect dual component dry tone process. Paper copy sizes shall be a maximum of 11 inches by 17 inches and a minimum of 4.25 inches by 5.5 inches. The machine shall have a halogen lamp light source and an automatic sheet feed (single cassette). Initially supply four reams (500 sheets per ream) of white copying paper and furnish a complete maintenance service contract/agreement for the machine.
- c. One personal computer, minimum 433 megahertz, 4 gigabyte hard drive, 64 megabytes of RAM, CD ROM Reader; 17" monitor (26 dot pitch maximum), mouse and keyboard. The software provided with the computer shall be Microsoft "Windows 95" or better and Microsoft "Office Professional" or approved equivalent.
- d. One laser printer, Hewlett Packard (HP) 4000N or approved equivalent.

#### 2.2.7 Maintenance.

The Contractor shall maintain the field office for the life of the contract. The Contractor shall be responsible for maintaining and paying for all costs associated with the following services:

- a. Supplies. Toilet paper, paper toweling, paper and supplies for the FAX and copy machines shall be provided. Supply water for the drinking water dispenser. Supply water for the lavatory if a service connection is not provided for potable water.
- b. Maintenance of office equipment. Include a maintenance service contract/agreement for operation of the Fax and Copy machines.
- c. Janitorial Service. The Contractor shall provide daily janitorial service and provide all janitorial and sanitary supplies as well as trash removal service.
- d. Snow removal. Maintenance of site access including snow removal service is the responsibility of the contractor.

### PART 3 EXECUTION

### 3.1 CLEANUP

Construction debris, waste materials, packaging material and the like shall be removed from the work site. Any dirt or mud which is tracked onto paved or surfaced roadways shall be cleaned away. Materials resulting from demolition activities which are salvageable shall be stored within the fenced area described above or at the supplemental storage area. Stored material not in trailers, whether new or salvaged, shall be neatly stacked when stored.


### 3.2 RESTORATION OF STORAGE AREA

Upon completion of the project and after removal of trailers, materials, and equipment from within the fenced area, the fence shall be removed and will become the property of the Contractor. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition. Gravel used to traverse grassed areas shall be removed and the area restored to its original condition, including top soil and seeding as necessary.

-- End of Section --

## PROJECT SIGN

The graphic format for this 4' x 6' sign panel follows the legend guidelines and layout as specified below. The large 4' x 4' section of the panel on the right is to be white with black legend. A 2' x 4' decal provided by the Corps shall be placed on the left side of the sign panel.



### Project Description:

One to three line project title legend describes the work being done under this contract.  
Color: Black; Typeface: 3" Helvetica Bold; Maximum line length: 42".

### Project Name:


One to three line identification of project or facility.  
Color: Black; Typeface: 1.5" Helvetica Bold; Maximum line length: 42".  
Cross-align the first line of PROJECT NAME with the first line of the Corps Signature as shown.

### Contractor:

One to five line identification of prime contractors including: type (architect, general contractor, etc.), corporate or firm name, city, state.  
Color: Black; Typeface: 1.25" Helvetica Bold; Maximum line length: 21".

All typography is flush left and ragged right, upper and lower case with initial capitals only as shown. Letter and word spacing to follow Corps Standards (EP 310-1-6a and 6b).

## SAFETY SIGN




All typography is flush left and rag right, upper and lower case with initial capitals only as shown. Letter and word spacing to follow Corps Standards (EP 310-1-6a and 6b).

Legend Group 1: Standard two-line title "Safety is a Job Requirement" with (8" od.) Safety Green First Aid logo. Typeface: 3" Helvetica Bold; Color: Black.

Legend Group 2: One- to two-line project title legend describes the work being done under this contract and name of host project. Typeface: 1.5" Helvetica Regular; Color: Black; Maximum line length: 42".


Legend Group 3: One- to two-line identification: name of prime contractor and city, state address. Typeface: 1.5" Helvetica Regular; Color: Black; Maximum line length: 42".

Legend Group 4: Standard safety record captions as shown. Typeface: 1.25" Helvetica Regular; Color: Black.



Replaceable numbers are to be mounted on white 0.060 aluminum plates and screw-mounted to background. Typeface: 3" Helvetica Regular; Color: Black; Plate size: 2.5" x 4.5".

## SIGN ERECTION DETAILS



SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01567

MINNESOTA POLLUTANT DISCHARGE ELIMINATION SYSTEM

PART 1 GENERAL

1.1 GENERAL

1.1.1 Definitions

1.1.2 Contract Drawings

1.2 REFERENCES

1.3 SUBMITTALS

1.4 PERMIT COMPLIANCE AND ADDITIONAL REQUIREMENTS

1.4.1 Schedule

1.4.2 Temporary erosion and sediment control plan

1.4.3 Application

1.4.4 Permanent erosion and sediment control plan

PART 2 PRODUCTS

2.1 SILT FENCE

2.2 STRAW BALES

2.3 OTHER PRODUCTS

PART 3 EXECUTION

3.1 IMPLEMENTATION

3.2 MAINTENANCE

3.3 RECORDS

3.4 ATTACHMENTS

-- End of Section Table of Contents --

## SECTION 01567

### MINNESOTA POLLUTANT DISCHARGE ELIMINATION SYSTEM

#### PART 1 GENERAL

##### 1.1 GENERAL

This section covers best management practices to be implemented for prevention of storm water pollution as required by the National Pollutant Discharge Elimination System (NPDES). The Minnesota Pollution Control Agency is responsible for administering permits for NPDES in the state of Minnesota. The Government has determined that the project work included under this contract requires NPDES permitting. The requirements herein supplement those covered in SECTION 01355: ENVIRONMENTAL PROTECTION.

##### 1.1.1 Definitions

The following terms apply to this specification and the general permit, unless redefined in subsequent paragraphs.

- a. "Plan" means the Temporary Erosion and Sediment Control Plan.
- b. "EPA" means the United States Environmental Protection Agency.
- c. "MPCA" means the Minnesota Pollution Control Agency.
- d. "NPDES" means the National Pollutant Discharge Elimination System.
- e. "MPDES" means the Minnesota Pollutant Discharge Elimination System.
- f. "Owner" as referred to in the general permit shall mean the Federal Government.
- g. "Permittees" as referred to in the general permit shall mean the Federal Government and Contractor.
- h. "General Permit" means the general permit authorization to discharge storm water associated with a construction activity under the National Pollutant Discharge Elimination System/State Disposal System Permit Program.
- j. "BMP" means Best Management Practices.

##### 1.1.2 Contract Drawings

The following features are shown on or can be determined from the contract drawings:

- a. The drainage patterns and approximate slopes anticipated after the major grading activities.
- b. Areas of soil disturbance.
- c. The location(s) where stabilization practices are expected to occur.
- d. Typical details showing suggested Best Management Practices (BMP's) for erosion and sediment control.
- e. Waters of the State.
- f. Final site stabilization.



## 1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

### ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA/832/R-92/005	Storm Water Management for Construction Activities - Developing Pollution Prevention Plans and Best Management Practices
------------------	--

### MINNESOTA DEPARTMENT OF TRANSPORTATION

MNDOT 3885	Standard Specifications for Construction (1995 Edition), Erosion Control Blankets
MNDOT 3886	Standard Specifications for Construction (1995 Edition), Silt Fence
MNDOT 3887	Standard Specifications for Construction (1995 Edition), Flotation Silt Curtain

## 1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

### SD-01 Preconstruction Submittals

Application; G,PM

A copy of the Application for General Storm Water Permit for Construction Activity (MPCA Form PQ00641) shall be submitted to the Contracting Officer at the same time it is transmitted to the state.

### SD-02 Shop Drawings

Temporary Erosion And Sediment Control Plan;

A specific Temporary Erosion and Sediment Control Plan shall be submitted in accordance with PARAGRAPH: PERMIT COMPLIANCE AND ADDITIONAL REQUIREMENTS.

### SD-11 Closeout Submittals

Notice of Termination;

A copy of the notice of termination shall be submitted to the

Contracting Officer at the same time it is transmitted to the state.

#### 1.4 PERMIT COMPLIANCE AND ADDITIONAL REQUIREMENTS

The Contractor shall comply with the requirements of General Permit No. MNR100000. The following define additional requirements and clarify which requirements of the General Permit are to be performed by either the Contractor, the Government, or both.

##### 1.4.1 Schedule

No contract project construction activities which require an NPDES permit may commence until the MPDES permit is valid.

##### 1.4.2 Temporary erosion and sediment control plan

The contract drawings show typical details of suggested best management practices (BMP's) for erosion and sediment control taken from EPA/832/R-92/005. The BMP's, together with applicable portions of the site drawings and specifications form an initial plan for temporary erosion and sediment control. The Contractor shall finalize and implement the plan. The finalized plan, together with documentation, shall be in accordance with the general permit. The plan shall be maintained at the site and made available to federal, state, and local officials as requested. The Contractor shall determine the specific BMP's for erosion and sediment control (including the types, locations, and installation scheduling of erosion and sediment controls). These BMP's and corresponding material specifications and shop drawings shall be included in the Plan.

##### 1.4.3 Application

The Application for General Storm Water Permit for Construction Activity must be signed by the Government and the Contractor. A blank copy of the application form is included at the end of this section. Immediately after contract award, the Contractor shall complete parts I, II and V of the application form, obtain signature by the Government, and submit the form to the state. The application shall be post marked at least 48 hours in advance of any ground breaking activities. The Contractor is responsible for payment of the application fee.

##### 1.4.4 Permanent erosion and sediment control plan

The Government has developed the Permanent Erosion and Sediment Control Plan and will maintain availability of the plan to federal, state, and local officials as required in the General Permit.

## PART 2 PRODUCTS

### 2.1 SILT FENCE

Silt fence shall be manufactured and installed as shown on drawings. On level sites with minimal potential for sediment loading, the wire fabric

may be omitted. Fabric for silt fence shall conform to requirements given in MNDOT 3886.

## 2.2 STRAW BALES

Straw shall be baled from oats, wheat, rye, barley, rice, or other coarse fiber vegetation that will percolate water. Hay baled from grass, alfalfa and clover is not acceptable.

## 2.3 OTHER PRODUCTS

Any products proposed for use that are not included on drawing Z2-22 shall be described fully, with catalog cuts and manufacturer's instructions for use, in the temporary erosion and sediment control plan. Other products, if proposed in the final plan, shall meet the following requirements:

Erosion control blankets shall meet MNDOT 3885  
Floatation Silt Curtain shall meet MNDOT 3887

## PART 3 EXECUTION

As between the Government and the Contractor, the Contractor shall be responsible for fulfilling the obligations of the general permit for the following sections:

Part I-C: Records  
Part I-D: Erosion and Sediment Control During Construction  
Part I-E: Inspection and Maintenance  
Appendix A: Temporary Erosion and Sediment Control Plan

## 3.1 IMPLEMENTATION

The Contractor shall install the sediment and erosion control system in accordance with the plan submitted to the Contracting Officer. The BMP's shall be modified if inspection indicates distress to the system or reveals unforeseen circumstances, or if directed by the Contracting Officer. Any updates to the plan shall be recorded. Permanent stabilization shall be initiated as soon as practicable in any portion of the site where construction activities are complete.

## 3.2 MAINTENANCE

The Contractor shall be responsible for implementing and managing the erosion and sediment control BMP's before and during the construction activities; and ensure that the Plan will be implemented and stay in effect until the work has been completed, the entire work site has undergone final stabilization, and a Notice of Termination has been submitted to the Contracting Officer and the state permitting authority.

## 3.3 RECORDS

The contractor shall record on CQC reports: (1) dates when major stripping and grading activities occur, (2) dates when construction activities

temporarily or permanently cease on a portion of the site,(3) when permanent stabilization practices are initiated, and (4) activities associated with inspection and maintenance.

#### 3.4 ATTACHMENTS

Application for General Storm Water Permit for Construction Activity (MDNR Form PQ00641 with instructions) 4 Pages


MPDES [General] Permit No. MN R100000 21 Pages

-- End of Section --



# Application for General Storm Water Permit for Construction Activity (#MNR100000)

Minnesota Pollution Control Agency  
520 Lafayette Road North; St. Paul, MN 55155-4194



## I. Construction Site Information

1. Name of project: \_\_\_\_\_
2. Brief description of where the construction activity occurs (please include address, if available):  
\_\_\_\_\_  
\_\_\_\_\_
3. Indicate ALL cities, counties, and townships where the construction activity will take place:  
\_\_\_\_\_  
\_\_\_\_\_
4. Name of waterbody(s) that will receive storm water from the construction site:  
\_\_\_\_\_  
\_\_\_\_\_
5. Project start date: \_\_\_\_\_ Project completion date: \_\_\_\_\_ Area to be disturbed by project: \_\_\_\_\_  
(in acres)

## II. Prerequisites for Applying for a Permit

For the following questions, please refer to the **NPDES General Storm Water Permit** (MNR100000).

A "No" answer for any question will result in this form being returned to the owner with no permit issued to authorize the construction activity. This application will need to be completed and returned to the MPCA before a permit to authorize the construction activity may be issued.

6. Has a **Temporary Erosion and Sediment Control Plan** been developed for this project in accordance with Appendix A and incorporated into this project's final plans and specifications? Yes ☐ No ☐
7. Has a **Permanent Erosion and Sediment Control Plan** been developed for this project in accordance with Appendix B and incorporated into this project's final plans and specifications? Yes ☐ No ☐
8. Has the Application Fee been enclosed? Yes ☐ No ☐

## III. Owner Information

Name \_\_\_\_\_ Telephone \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip Code \_\_\_\_\_

Contact Person \_\_\_\_\_ Telephone \_\_\_\_\_

#### IV. Owner Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person, or persons, who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete (Minnesota Rules part 7001.0070).

I also certify under penalty of law that I have read, understood, and accepted all terms and conditions of the National Pollutant Discharge Elimination System (NPDES) General Storm Water permit (MNR100000) that authorizes storm water discharges associated with the construction site identified on the front side of this form.

I understand that as a permittee, I am legally accountable under the Clean Water Act, to ensure compliance with the terms and conditions of the NPDES General Storm Water Permit (MNR100000).

I also understand that MPCA enforcement actions (pursuant to Minnesota Statutes sections 115.07, 116.072, and 609.71 and Section 309 of the Clean Water Act) may be taken against my company if the terms and conditions of the NPDES General Storm Water Permit (MNR100000) are not met.

Printed Name

Title (Manager, CEO, etc.)

Authorized Signature

Date

#### V. General Contractor Certification

I certify under penalty of law that I have read, understood, and accepted all terms and conditions of the National Pollutant Discharge Elimination System (NPDES) General Storm Water permit (MNR100000) that authorizes storm water discharges associated with the construction site identified on this form.

I understand that for Parts I.B. through I.E, Appendix C, and Appendix D of the General Storm Water Permit (MNR100000) I am becoming a co-permittee with the owner of the facility for which I have been contracted to perform professional construction services. As a co-permittee I understand that my company is legally accountable, under the Clean Water Act, to ensure compliance with the terms and conditions of the General Storm Water Permit (MNR100000).

I also understand that MPCA enforcement actions (pursuant to Minnesota Statutes sections 115.07, 116.072, and 609.71 and Section 309 of the Clean Water Act) may be taken against my company if the terms and conditions of the NPDES General Storm Water Permit (MNR100000) for which I am a co-permittee, are not met.

Company or Firm

Telephone

Printed Name

Title (Manager, CEO, etc.)

Authorized Signature

Date

Address


City

State

Zip Code

Contact Person

Telephone



# **Application Instructions for General Storm Water Permit**

## **CONSTRUCTION ACTIVITY**




### **Minnesota Pollution Control Agency**

520 Lafayette Road North  
St. Paul, MN 55155-4194

# Application Process for Coverage Under Storm Water Permit for Construction Activity

Applicants still need to seek approval through required permitting process at the local, state, and federal levels.



For additional information call:

(612) 296-7219 or  
1-800-657-3804

People with speech or hearing impairments may call (612) 282-5332 or 1-800-627-3529



**Minnesota Pollution Control Agency****GENERAL PERMIT****AUTHORIZATION TO DISCHARGE****STORM WATER ASSOCIATED WITH A CONSTRUCTION****ACTIVITY UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION****SYSTEM/STATE DISPOSAL SYSTEM PERMIT PROGRAM****ISSUANCE DATE: September 4, 1998****EXPIRATION DATE: September 4, 2003**

In compliance with the provisions of the Clean Water Act, as amended, (33 U.S.C. 1251 et seq.; hereinafter, the "Act"); 40 CFR 122, 123, and 124, as amended, et seq.; Minnesota Statutes Chapters 115 and 116, as amended, and Minnesota Rules Chapter 7001:

**This permit establishes conditions for discharging storm water to waters of the state from construction activities which disturb five or more acres of total land area.**

**This permit DOES NOT authorize:**

- 1) Discharges or releases that are not storm water as defined on Page 18 (see "Prohibitions" on Page 14 of this permit).
- 2) The placement of fill into waters of the state.

Unless notified by the Agency to the contrary, applicants who submit a complete application form in accordance with the requirements of this permit are authorized to discharge storm water from construction sites under the terms and conditions of this permit 48 hours after the date the application is postmarked.

Coverage under this permit will remain in effect until construction is complete, the site has undergone final stabilization, all maintenance activities required in Part I.E. have been completed, and the Permittee has submitted a Notice of Termination, regardless of the above expiration date.

Signature: John N. Holck, Manager  
South District

for

Peder A. Larson  
Commissioner

Operations &amp; Planning/Major Facilities

Minnesota Pollution Control Agency

If you have questions on this permit, including the specific permit requirements, permit reporting or permit compliance status, please contact:

**Minnesota Pollution Control Agency  
Metro District, Storm Water Permit Program  
520 Lafayette Road North  
St. Paul, MN 55155-4194  
Telephone (651) 296-3890  
Fax (651) 297-8701**

## Table of Contents

	Page
<b>I. REQUIREMENTS OF THIS PERMIT . . . . .</b>	<b>3</b>
A) Prerequisites for Submitting a Permit Application. . . . .	3
B) Application for Coverage . . . . .	3
C) Records to be Kept On Site . . . . .	4
D) Erosion and Sediment Control During Construction . . . . .	5
1) Erosion Control . . . . .	5
2) Sediment Control . . . . .	6
E) Inspections and Maintenance. . . . .	7
F) Duration of Permit Coverage. . . . .	8
G) Appendices Incorporated by Reference . . . . .	8
<b>II. APPENDICES</b>	
APPENDIX A - TEMPORARY EROSION AND SEDIMENT CONTROL PLAN	
A) Goal . . . . .	9
B) Assigning Responsibilities . . . . .	9
C) Plan Contents. . . . .	9
D) Final Plans and Specifications . . . . .	10
E) Plan Retention . . . . .	10
F) Changes to the Temporary Erosion and Sediment Control Plan . . . . .	10
APPENDIX B - PERMANENT EROSION AND SEDIMENT CONTROL PLAN	
A) Goal . . . . .	11
B) Assigning Responsibilities . . . . .	11
C) Plan Contents. . . . .	11
D) Final Plans and Specifications . . . . .	13
E) Plan Retention . . . . .	13
F) Changes to the Permanent Erosion and Sediment Control Plan . . . . .	13
APPENDIX C - PROVISIONS	
A) Applicability Criteria . . . . .	14
B) MPCA Address . . . . .	14
C) Response . . . . .	14
D) Authorized Discharges. . . . .	14
E) Prohibitions . . . . .	14
F) Definitions . . . . .	15
APPENDIX D - RESPONSIBILITIES	
A) Transfer Ownership of Control . . . . .	19
B) Permit Modification . . . . .	19
C) Right of Entry . . . . .	19
D) Civil and Criminal Liability . . . . .	20
E) Oil and Hazardous Substance Liability . . . . .	20
F) Liability Exemption . . . . .	20
G) Minnesota Laws . . . . .	20
H) Property Rights . . . . .	20
I) Severability . . . . .	20
J) NPDES/SDS Rules . . . . .	21
K) Other Statutes, Rules, and Ordinances. . . . .	21
L) More Stringent Rules . . . . .	21
M) Agency Obligation . . . . .	21

I. REQUIREMENTS OF THIS PERMIT

A. PREREQUISITES FOR SUBMITTING A PERMIT APPLICATION

Failure to complete the following prerequisites prior to submitting the **application** will result in the **application** being returned, and the construction project NOT authorized by this **permit**.

1. The **owner** must develop a Temporary **Erosion and Sediment Control** Plan in accordance with "Appendix A." The plan requirements must be incorporated into the project's **final plans and specifications** and implemented as part of the project.
2. The **owner** must develop a Permanent **Erosion and Sediment Control** Plan in accordance with "Appendix B." The plan requirements must be incorporated into the project's **final plans and specifications** and implemented as part of the project.

The above plans are NOT to be submitted to the Agency but are to be retained by the owner in accordance with Appendices A and B; "Plan Retention."

B. APPLICATION FOR COVERAGE

1. The **owner** and **general contractor** are responsible for submitting a completed **application** form (or a photocopy thereof) to the Minnesota Pollution Control Agency (MPCA) for each project which disturbs five (5) or more acres of land.
2. The **owner** who signs the **application** is responsible for compliance with all terms and conditions of this **permit**. The **general contractor** who signs the **application** is a Co-Permittee for Parts I.B. through I.E., Appendix C, and Appendix D of this **permit**. and is responsible for compliance with those portions of this **permit**.
3. This permit will become effective 48 hours after the postmarked date of the completed **application** form containing "Yes" responses to questions 6, 7, and 8. A "No" response to question 6, 7, or 8 will result in the application being returned to the owner, and no permit will be issued to authorize the construction. No construction which requires an NPDES permit may commence unless authorized by an NPDES permit.
4. Permittees will receive a "Notice of Storm Water Permit Coverage" card acknowledging permit coverage within 30 days of the postmarked date of the completed **application**. (See I.D.3. for posting requirements.) A photocopy of this card must be provided by the **owner** to the **local permitting authority**, where applicable, within 14 days of receipt.

C. RECORDS

1. The project's **final plans and specifications** which incorporate the requirements of the Temporary Erosion and Sediment Control Plan and Permanent Erosion and Sediment Control Plan must be:
  - a. available at the construction site in either the field office, or, inspector's vehicle, or contractor's vehicle, and,
  - b. available to federal, state, and local officials (in accordance with Appendix D, Subpart C) for inspection for the duration of this permit.
2. The following plans/records must be made available to federal, state and local officials within 24 hours of request (in accordance with Appendix D, Subpart C.) for the duration of the permit:
  - a. Temporary Erosion and Sediment Control Plan developed in accordance with Part I.A.1. (if a separate document from the project's **final plans and specifications**).
  - b. Permanent Erosion and Sediment Control Plan developed in accordance with Part I.A.2.
  - c. Records of all inspections (see Part I.E.). Records shall include:
    - 1) Date and time of inspections,
    - 2) Findings of inspections,
    - 3) Corrective actions taken (including dates and times)
    - 4) Documentation of changes to the Temporary Erosion and Sediment Control Plan made during construction.
  - d. Date of all rainfall events.
3. The "Notice of Storm Water Permit Coverage" card shall be posted at any of the following locations:
  - a. construction site entrance and visible from the nearest public roadway
  - b. visible from the nearest public roadway, where no construction site entrance exists
  - c. field office (if applicable)
  - d. for linear utility and non-contiguous municipal projects, at the office responsible for project administration.

D. EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION

1. Erosion Control

- a. The **Permittee(s)** shall use, where possible, horizontal slope grading, construction phasing, and other construction practices that minimize **erosion**.
- b. Unless precluded by snow cover, all **exposed soil areas\*** with a continuous positive slope within 100 lineal feet from a water of the state, or from a curb, gutter, storm sewer inlet, temporary or permanent drainage ditch or other **storm water** conveyance system, which is connected to a water of the state, shall have **temporary protection or permanent cover** for the **exposed soil areas** within the following time frames:

<u>Type of Slope</u>	Temporary protection or permanent cover where the area has not been, or will not be, worked by the contractor for:
Steeper than 3:1	7 days
10:1 to 3:1	14 days
Flatter than 10:1	21 days

\*For the purposes of this provision, **exposed soil areas** do not include stockpiles or surcharge areas of sand, gravel, aggregate, concrete or bituminous.

- c. The bottom of any temporary or permanent drainage ditch constructed to drain water from a construction site must be stabilized within 100 lineal feet from a water of the state. Stabilization must be initiated within 24 hours of connecting the drainage ditch to **a water of the state**, existing gutter, storm sewer inlet, drainage ditch, or other **storm water** conveyance system which discharges to **waters of the state** and completed within five calendar days.
- d. Prior to connecting any pipe to a **water of the state** or drainage ditch, the pipe's outlet must be provided with temporary or permanent **energy dissipation** to prevent erosion.

2. Sediment Control

- a. **Sediment control best management practices (BMPs)**, which prevent **sediment** from entering a **water of the state**, gutter, storm sewer inlet, ditch or other storm water conveyance system, shall be established on all down-gradient perimeters before any up-gradient land disturbing activities begin, and shall remain in place until final stabilization has been established.
- b. The Permittee shall minimize vehicle tracking of **sediment** or **soil** off site at locations where vehicles exit the construction site onto **paved surfaces**.
- c. Where 10 or more contiguous acres of **exposed soil** are contributing to a discernible point of **discharge**, temporary sedimentation basins\* must be provided prior to the runoff leaving the construction site or entering **waters of the state**.

These sedimentation basins shall comply with the following:

- 1) Basins shall provide 1800 ft<sup>3</sup> per acre drained of hydraulic storage below the outlet pipe. For roadways, the use of adjacent drainage ditches with riser pipes to accomplish this is acceptable.
- 2) Basin outlets shall be designed to prevent short circuiting and the **discharge** of floating debris. The outlet should consist of a perforated riser pipe wrapped with filter fabric and covered with crushed gravel. The perforated riser pipe should be designed to allow complete basin drawdown.

\*While recommended, this provision will not be required for:

- 1) work on existing roadways where the 10 acre disturbed common drainage area is served by an existing storm sewer which is daylighted off the road's right-of-way,  
**or,**
- 2) proximity to bedrock or vertical relief precludes it,  
**or,**
- 3) final stabilization will be established within 30 days of the initiation of construction activity.

E. INSPECTIONS AND MAINTENANCE

1. Except where work has been suspended due to frozen ground conditions, the **Permittee(s)** shall inspect the construction site once every seven (7) days and within 24 hours after every rain event, which results in runoff leaving the construction site or entering **waters of the state**. The **Permittee** shall investigate and comply with the following inspection and maintenance requirements:

- a. Inspection Requirement: All **erosion** and perimeter **sediment control BMPs** to ensure integrity and effectiveness.

Maintenance Requirement: All nonfunctional perimeter **sediment control BMPs** shall be repaired when the sediment reaches 1/3 of the height, or replaced, or supplemented with functional **BMPs** within 24 hours of discovery. All nonfunctional **erosion control BMPs** shall be repaired, replaced, or supplemented with functional **BMPs** as soon as field conditions allow access.

- b. Inspection Requirement: All temporary sedimentation basins to ensure effectiveness.

Maintenance Requirement: When the depth of sediment collected in the basin reaches 1/2 the height of the riser, or 1/2 the storage volume, the basin shall be drained and the sediment removed. Drainage and removal shall be completed within 72 hours of discovery, or as soon as field conditions allow access.

- c. Inspection Requirement: Drainage ditches and other **waters of the state** for evidence of **sediment** leaving the site.

Maintenance Requirement: Unless the project has received approval or certification for depositing fill into waters of the state, the **Permittee** shall remove all deltas and **sediment** deposited in drainage ways, catch basins, or **waters of the state**, and restabilize the areas where **sediment** removal results in **exposed soil**. The removal and stabilization shall take place within seven (7) days of discovery unless precluded by legal, regulatory, or physical access restraints. If precluded, removal and stabilization must take place within seven calendar days of obtaining access. The **Permittee** is responsible for contacting all local, regional, state and federal authorities prior to working in waters of the state, and receiving any applicable permits.

- d. Inspection Requirement: Construction site vehicle exit locations for evidence of off-site **sediment** tracking onto paved **surfaces**.

Maintenance Requirement: Tracked **sediment** shall be removed from paved **surfaces**, which do not drain back into the construction site, within 24 hours of discovery.

2. Where parts of the construction site have undergone **final stabilization**, but work remains on other parts of the site, inspections of the stabilized areas may be reduced to once per month.
3. Where work has been suspended due to frozen ground conditions, the inspections and maintenance required in Part I.E.1. above shall take place as soon as weather conditions warrant or prior to resuming construction.
4. Unless required to remain in place by the **owner** or **local permitting authority**, all temporary synthetic, structural, and nonbiodegradable **erosion** and **sediment control BMPs** shall be removed after the site has undergone **final stabilization**.
5. After the entire project has undergone **final stabilization**, all temporary sedimentation basins to be used as permanent water quality management basins must be cleaned out by the **Permittee** to provide the sediment storage capacity required in Part I.D.2.c.2. **Permittees** are responsible for the maintenance of water quality management **BMPs** until construction is complete, the site has undergone **final stabilization**, and a **Notice of Termination** has been submitted to the **Agency**.

F. DURATION OF PERMIT COVERAGE

The **owner** and **general contractor** are responsible for complying with their respective portions of this permit until construction is complete, all maintenance activities required in Part I.E. are complete, the site has undergone **final stabilization** and a **Notice of Termination** is submitted to the **Agency**.

G. APPENDICES INCORPORATED BY REFERENCE

Appendices A, B, C, and D are incorporated into this permit by reference and are made both integral and enforceable parts of this permit.



## APPENDIX A

## TEMPORARY EROSION AND SEDIMENT CONTROL PLAN

(Completed prior to submittal of an application)

- A. GOAL: The goal of the Temporary Erosion and Sediment Control Plan is to prevent **sediment** from entering **waters of the state** during construction. The **owner** shall incorporate **Best Management Practices (BMPs)** into the project's **final plans and specifications**, which are designed to meet this goal and comply with Parts I.D. and I.E. of this **permit**. While the general requirements are identified in Parts I.D. and I.E. of this **permit**, it is the **owner's** responsibility to select the appropriate **BMPs** which satisfy these requirements.

B. ASSIGNING RESPONSIBILITY

When developing bidding documents or other contracts, the **owner** must identify who will implement and manage the **erosion and sediment control BMPs** before and during construction; and ensure that the plan will be implemented and stay in effect until the construction project is complete, the entire site has undergone **final stabilization**, and a **Notice of Termination** has been submitted to the Agency. In addition, the **final plans and specifications** must clearly identify who will be responsible for the maintenance requirements identified in Part I.E. of this permit.

C. PLAN CONTENTS

The Temporary **Erosion and Sediment Control Plan**, if developed as a document separate from the project's **final plans and specifications**, must be prepared for the proposed project. The plan must contain appropriate **BMPs** which comply with Parts I.D. and I.E. of this permit and contain **standard plates** and/or specifications of these **BMPs**.

1. **Standard plates** and/or specifications must be provided for all **BMPs**, selected by the designer to be used on the project, and at a minimum, must include the following:
  - a. perimeter sediment control
  - b. placement and type of **temporary cover**
2. Where applicable, **standard plates** and/or specifications must also be provided for the following:
  - a. horizontal slope grading
  - b. proposed stabilized vehicle entrances
  - c. temporary sedimentation basins
  - d. storm sewer pipe outlet energy dissipation
  - e. storm sewer inlet control
  - f. **erosion and sediment control** requirements for stockpile areas

D.

The above **standard plates** and/or specifications are to be incorporated into the project's **final plans and specifications**. In addition, the **final plans and specifications** shall clearly denote:

1. Location and type or the procedures to establish the location and type of all **erosion and sediment control BMPs**.
2. Existing and final grades, including dividing lines and direction of flow for all **storm water** runoff drainage areas located within the project limits.
3. Locations of areas not to be disturbed or areas where construction will be staged to minimize duration of **exposed soil areas**.
4. All **waters of the state**, including existing wetlands identified on the National Wetlands Inventory Map, within one-half mile from the exposed construction area which will receive direct storm water runoff from the construction site during construction.

Where waters of the state, including wetlands, which will receive the direct runoff will not fit on a plan sheet, they shall be identified with an arrow, indicating both direction and distance.

5. Timing for installation of all erosion and sediment control BMPs required in Part J.D.

E.

The owner shall keep a copy of the Temporary Erosion and Sediment Control Plan and all changes to it for three years after completion of the construction project.

F.

Changes in the plan made during construction to accommodate phased construction, sequenced work, timing issues, or changed site conditions are allowable provided Parts I.D. through I.E. are complied with.

## PERMANENT EROSION AND SEDIMENT CONTROL PLAN

A. GOAL: The goal of the Permanent Erosion and Sediment Control Plan is to protect Minnesota's water resources from pollutants generated from a project's ultimate development's impervious surfaces, change in land use, or changed ground cover.

When developing bidding documents or other contracts, the **owner** must identify who will maintain the water quality management **BMPs** until construction is complete, all maintenance activities required in Part I.E. are complete, the site has undergone **final stabilization**, and a **Notice of Termination** has been submitted to the **Agency**.

The Permanent Erosion and Sediment Control Plan must be prepared for the proposed project, and may be developed as a separate document from the **final plans and specifications**. The plan must contain appropriate **BMPs** which satisfy the above goal, and contain **standard plates** and/or specifications of these **BMPs**. These **standard plates** and specifications must be incorporated into the project's **final plans and specifications**. At a minimum, the plan must contain:

1. Land feature changes (in acres) for both **before** and **after** construction:
  - a. Total project area;
  - b. Total **impervious surface** area of project;
  - c. Total pervious area of project;
  - d. Total estimated **impervious surface** area of ultimate development;
  - e. Total estimated pervious area of ultimate development;

2. **Standard plates** and/or specifications of permanent erosion and sediment control BMPs below (Appendix B. C. 2a. 2b. and 2c.):

Where a project's ultimate development replaces surface vegetation with one or more acres of cumulative impervious surface and all runoff has not been accounted for in a local unit of government's existing storm water management plan or practice, the runoff shall be discharged to a wet sedimentation basin\* prior to entering waters of the state.

Except as provided in 2) below ("Reconstruction or Work on Existing Roadways"), the wet sedimentation basin shall be based on the project's ultimate development and comply with the following requirements:

- ## 2) Reconstruction or Work on Existing Roadways

b. Permanent Erosion Control

- ### c. Treatment

All **boldfaced** terms are defined in "Definitions", Pages 15 through 18.

D. FINAL PLANS AND SPECIFICATIONS

The above standard plates and/or specifications are to be incorporated into the project's final plans and specifications. In addition, the final plans and specifications shall clearly denote:

1. Location and type of all permanent erosion and sediment control BMPs (Appendix B.C.2a., 2b. and 2c.).
2. The plan sheets must clearly identify all **waters of the state**, including wetlands identified on the National Wetlands Inventory Map within and one-half mile from the construction area which will receive direct **storm water** runoff from the construction site after construction is complete.

Where the **waters of the state** which will receive the direct runoff and will not fit on the plan sheet, the resource shall be identified with an arrow, indicating both direction and distance.

3. Methods to be used for final stabilization of all exposed soil areas. For linear utility and roadway projects, final stabilization is not required on agricultural land which will be tilled within one year of project completion.

E. PLAN RETENTION

The owner shall keep a copy of the Permanent Erosion and Sediment Control Plan and all changes to it for three years after completion of the construction project.

F. CHANGES TO THE PERMANENT EROSION AND SEDIMENT CONTROL PLAN

Changes in the plan made during construction to accommodate changed site conditions are allowable provided all of Appendix B. is complied with.

APPENDIX C

PROVISIONS

A. APPLICABILITY CRITERIA

1. This permit covers storm water discharges associated with a construction activity which disturb **five (5) or more acres of land** in all areas of the state of Minnesota, except for agricultural/silvicultural activities.
2. This is a National Pollutant Discharge Elimination System/State Disposal System general permit.
3. If the Commissioner determines that storm water discharges associated with a construction activity, or other activities, are contributing to a violation of a water quality standard or would be more appropriately regulated by an individual permit, the Commissioner may require a Permittee to be covered by an individual storm water discharge permit. The Commissioner may require a Permittee to develop and implement specific best management practices. Upon issuance of an individual permit, this general permit would no longer apply.
4. A permit applicant, or Permittee, may request an individual permit.

B. MPCA ADDRESS

Submit all forms, correspondence, reports, etc. to the following address:

Minnesota Pollution Control Agency  
Water Quality Division  
Attn: Construction Activity Storm Water Program  
520 Lafayette Road North  
St. Paul, Minnesota 55155-4194

C. RESPONSE

The Permittee shall respond to Agency requests for submittal of temporary and permanent erosion and sediment control plans and water quality management plans, certificates, reports, records, or other information required by this permit. Upon request, the Permittee shall also provide a copy of this information to the local permitting authority and municipal storm sewer operator.

D. AUTHORIZED DISCHARGES

All discharges of storm water associated with a construction activity shall be composed entirely of storm water.

E. PROHIBITIONS

Discharges of any material other than storm water, such as vehicle and equipment maintenance spills; wash water; oil and other hazardous substances are prohibited by this permit.

F. DEFINITIONS

1. "Act" means the Clean Water Act (formerly the Federal Water Pollution Control Act), United States Code, Title 33, Sections 1251 et seq., as amended.
2. "Agency" means the Minnesota Pollution Control Agency (MPCA).
3. "Application" means a completed application for activities regulated by this permit. Application forms are available from the Agency.
4. "Best Management Practices (BMPs)" means erosion and sediment control and water quality management practices that are the most effective and practicable means of controlling, preventing, and minimizing degradation of surface water, including construction-phasing, minimizing the length of time soil areas are exposed, prohibitions, and other management practices published by state or designated areawide planning agencies.

Examples of BMPs can be found in Protecting Water Quality in Urban Areas, Minnesota Pollution Control Agency 1989, and Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices, U.S. Environmental Protection Agency 1992 as a reference for BMPs, and Erosion Control Design Manual, Minnesota Department of Transportation, et al, 1993.

5. "Construction Activity" means a disturbance to the land that results in a change in the topography, existing soil cover (both vegetative and non-vegetative), or the existing soil topography which may result in accelerated storm water runoff, leading to soil erosion and movement of sediment into waters of the state. Examples can include clearing, grading, filling and excavating.
6. "Discharge" means the conveyance, channeling, runoff, or drainage, of storm water, including snow melt, from a construction site.
7. "Energy Dissipation" means methods employed at pipe outlets to prevent erosion. Examples include, but are not limited to; aprons, riprap, splash pads, and gabions which are designed to prevent erosion.
8. "Erosion" means the wearing away of soil by rainfall, surface water runoff, wind, or ice movement.
9. "Erosion Control" means methods employed to prevent erosion. Examples include soil stabilization practices, horizontal slope grading, temporary or permanent cover, and construction phasing.
10. "Exposed Soil Areas" means all areas of the construction site where the perennial vegetation (including trees, shrubs, and brush) has been removed. This includes topsoil stockpile areas, borrow areas and disposal areas within the construction site.

11. **"Final Plans and Specifications"** means the reports, prints, drawings, written descriptions, and clear technical requirements necessary to build a project used by the owner for the purposes of entering into a construction contract.
12. **"Final Stabilization"** means that all soil disturbing activities at the site have been completed, and that a uniform perennial vegetative cover with a density of 70 percent of the cover for unpaved areas and areas not covered by permanent structures has been established or equivalent permanent stabilization measures have been employed. Examples of vegetative cover practices can be found in Supplemental Specifications to the 1988 Standard Specifications for Construction (Minnesota Department of Transportation, 1991).
13. **"Five or more acres of total land area"** means any project that disturbs at least five acres of land measured by the project's construction corridor, excluding areas staked as not to be disturbed. If the project is less than five acres, but is part of larger common plan of development or sale (where multiple separate and distinct construction activities may be taking place at different times on different schedules but under one plan), it is defined as "five acres or more of total land area."
14. **"General Contractor"** means the party who signs the construction contract with the owner to construct the entire project described in the final plans and specifications. Where the construction project involves more than one contractor, the general contractor will be the party responsible for managing the entire project on behalf of the owner. In some cases, the owner may be the general contractor. In these cases, the owner will sign the permit application as the general contractor and would become the sole permittee.
15. **"Impervious Surface"** means a constructed hard surface that either prevents or retards the entry of water into the soil and causes water to run off the surface in greater quantities and at an increased rate of flow than prior to development. Examples include rooftops, sidewalks, patios, driveways, parking lots, storage areas, and concrete, asphalt, or gravel roads.
16. **"Local Permitting Authority"** means the township, county, municipality, conservation district, watershed district, watershed management organization, or other public entity which has the authority to review and approve construction activities.
17. **"Local Unit of Government's Existing Storm Water Management Plan or Practice"** means plans or practices developed by the local permitting authority under state law for the purposes of protecting water quality.



18. **"National Pollutant Discharge Elimination System (NPDES)"** means the program for issuing, modifying, revoking, reissuing, terminating, monitoring, and enforcing permits under the Clean Water Act (Sections 301, 318, 402, and 405) and United States Code Title 33, Sections 1317, 1328, 1342, and 1345.
19. **"Notice of Termination"** means notice to terminate coverage under this permit after construction is complete, the site has undergone stabilization, and all conditions of this permit have been satisfied. Notice of Termination forms are available from the Agency.
20. **"Owner"** means the person or party possessing the title of the land on which the construction activities will occur; or if the construction activity is for a lease holder, the party or individual identified as the lease holder; or the contracting government agency responsible for the construction activity.
21. **"Permanent Cover"** means final stabilization. Examples include grass, gravel, asphalt, and concrete.
22. **"Paved Surface"** means a constructed hard, smooth surface made of asphalt, concrete or other pavement material. Examples include, but are not limited to, roads, sidewalks, driveways and parking lots.
23. **"Permit"** means a National Pollutant Discharge Elimination System/ State Disposal System (NPDES/SDS) permit.
24. **"Permittee"** means a person, firm, or governmental agency or other institution who signs the application submitted to the Agency and is responsible for compliance with the terms and conditions of this permit.
25. **"Runoff Coefficient"** means the fraction of total precipitation that is not infiltrated into or otherwise retained by the soil, concrete, asphalt or other surface upon which it falls that will appear at the conveyance as runoff.
26. **"Sediment"** means the product of an erosion process; solid material both mineral and organic, that is in suspension, is being transported, or has been moved by water, air, or ice, and has come to rest on the earth's surface either above or below water level.
27. **"Sediment Control"** means methods employed to prevent sediment from leaving the site. Sediment control practices include silt fences, sediment traps, earth dikes, drainage swales, check dams, subsurface drains, pipe slope drains, storm drain inlet protection, and temporary or permanent sedimentation basins.
28. **"Soil"** means the unconsolidated mineral and organic mineral material on the immediate surface of the earth.

29. **"Stabilized"** means the exposed ground surface has been covered by staked sod, riprap, wood fiber blanket, or other material which prevents erosion from occurring. Grass seed is not stabilization.
30. **"Standard Plates"** means general drawings having or showing similar characteristics or qualities that are representative of a construction practice or activity.
31. **"Storm water"** means the precipitation runoff, storm water runoff, snow melt runoff, and any other surface runoff and drainage (defined in 40 CFR 122.26 [b][13]). Storm water does not include construction site dewatering.
32. **"Temporary Protection"** means methods employed to prevent erosion. Examples of temporary include; straw, wood fiber blanket, wood chips, and erosion netting.
33. **"Waters of the State"** means all streams, lakes, ponds, marshes, wetlands, watercourses, waterways, drainage systems and all other bodies or accumulations of waters, natural or artificial, public or private, which are contained within, flow through, or border upon the state or any portions thereof. Waters of the state do not include storm water detention basins, or wetlands constructed for the purposes of treating storm water, which do not discharge to surface waters.

APPENDIX D

RESPONSIBILITIES

A. TRANSFER OWNERSHIP OR CONTROL

This permit may not be assigned or transferred by the permit holder. Where a new general contractor is selected after the submittal of an application, or where the general contractor changes, a new application must be, in accordance with Part I.B., submitted to the Agency at least 48 hours prior to when the general contractor begins work at the site.

B. PERMIT MODIFICATION

After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to, the following:

1. Violation of any terms of this permit;
2. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
3. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge; or
4. Minn. Rules pts. 7001.0170 and 7001.0180.

C. RIGHT OF ENTRY

The Permittee shall, pursuant to Section 308 of the Act and Minnesota Statutes 115.04, allow representatives of the; Agency, local permitting authorities, local soil and water conservation districts, or municipality which operates the storm sewer system, upon presentation of credentials:

1. To enter upon the Permittee's premises where the construction activity is occurring for the purpose of obtaining information, examination of records, conducting surveys or investigations;
2. To bring such equipment upon the Permittee's premises as is necessary to conduct such surveys and investigations;
3. To examine and copy any books, papers, records, or memoranda pertaining to the storm water discharge.
4. To sample and monitor any substances or parameters at any location.

D. CIVIL AND CRIMINAL LIABILITY

Nothing in this permit shall be construed to relieve the Permittee from civil or criminal penalties for noncompliance with the terms and conditions provided herein.

E. OIL AND HAZARDOUS SUBSTANCE LIABILITY

Nothing in this permit shall be construed to preclude the installation of any legal action or relieve the Permittee from any responsibilities, liabilities, or penalties to which the Permittee is or may be subject to under Section 311 or the Act and Minn. Stat. chs. 115 and 116, as amended.

F. LIABILITY EXEMPTION

This permit authorizes the Permittee to perform the activities described herein within the conditions set forth. In issuing this permit, the State/Agency assumes no responsibility for any damage to persons, property or the environment caused by the activities authorized or undertaken pursuant to this permit. To the extent the state/agency may have any liability for the activities of its employees, that liability is explicitly limited to that provided in the Torts Claim Act, Minn. Stat. § 3.736.

G. MINNESOTA LAWS

Nothing in this permit shall be construed to preclude the installation of any legal or administrative proceedings or relieve the Permittee from any responsibilities, liabilities, or penalties for violation of effluent and water quality limitations not included in this permit or applicable laws or regulations.

H. PROPERTY RIGHTS

The issuance of this permit does not convey any property rights in either real or personal property, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state, or local laws or regulations.

I. SEVERABILITY

The provisions of this permit are severable, and if any provisions of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

J. NPDES/SDS RULE

The Permittee shall comply with the provisions of Minn. Rules pts. 7001.0150, subp. 3 and 7001.1090, subp. 1.A,B,C,H,I. This permit does not require the submittal of a data monitoring report.

K. OTHER STATUTES, RULES AND ORDINANCES

The Agency's issuance of a permit does not release the Permittee from any liability, penalty or duty imposed by Minnesota or federal statutes or local ordinances, except the obligation to obtain the permit.

L. MORE STRINGENT RULES

The Agency's issuance of a permit does not prevent the future adoption by the Agency of pollution control rules, standards, or orders more stringent than those now in existence and does not prevent the enforcement of these rules, standards or orders against the Permittee.

M. AGENCY OBLIGATION

The Agency's issuance of a permit does not obligate the Agency to enforce local laws, rules or plans beyond that authorized by Minnesota Statutes.